

CONCRETE

AND

CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

for Science and
Technology.

JULY 1957



3400A
VOL. LII. NO. 7

FIFTY-SECOND YEAR OF PUBLICATION

PRICE 1s. 9d.

ANNUAL SUBSCRIPTION 21s., POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Technical Training in the U.S.S.R.	225
Reinforced Concrete Structures in Berlin	227
Estimating the Size of Rectangular Sections By F. H. Turner	233
Design of Reinforced and Prestressed Bridges By Dr. Riccardo Morandi	237
Prestressed Concrete Bridge for Heavy Loads By E. A. L. Keith	247
Design of Silos	252
The Terminology of Prestressed Concrete	253
Aggregate from Pulverised-fuel Ash	255

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.



For over 60 years

this trade mark has stood for speed and
strength in reinforced concrete work.

DRAGON

(Brand)

PORTLAND CEMENT

Supplied by


THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.
PENARTH, SOUTH WALES

Telephone : Penarth 300

Telegrams : "Cement, Penarth"







Built in 6 days with Prometo Forms

This 100-foot high silo for the Liverpool Grain Storage and Transit Company Ltd., took exactly six days and nights to build. The Prometo Moving Forms rose under hydraulic pressure at a rate of 17-ft. per day. William Thornton are the sole U.K. licensees for this Swedish method of rapid and reliable monolithic construction in concrete.

William **THORNTON** & Sons Ltd

38 WELLINGTON ROAD - LIVERPOOL

Lark Lane 1921 (4 lines)

Telegrams: "Thornpool Liverpool"

YORKSHIRE HENNEBIQUE

Contracting Co. Ltd.

ESTABLISHED 1904

CIVIL ENGINEERING
CONTRACTORS


HEAD OFFICE :
HENNEBIQUE HOUSE
The Mount • York

Telephone : YORK 54656 (4 lines)

Branch Offices :


HULL : 30 WINCOLMLEE. Telephone : Hull 33501

LEEDS : ROYDS WORKS, LOWER WORTLEY, LEEDS 12. Telephone : Leeds 637891



Sugar Silos at King's Lynn for British Sugar Corporation Limited

Silo construction



LAING


John Laing and Son Limited

BUILDING AND CIVIL
ENGINEERING CONTRACTORS

GREAT BRITAIN • CANADA
UNION OF SOUTH AFRICA
RHODESIA

*Malt Silos at Ndola, Northern Rhodesia
for South African Breweries Limited*

BAR-BENDING EQUIPMENT




RAS.40 MODEL

This is a single-disc machine which is specially designed for an extraordinarily high rate of bending bars up to $1\frac{1}{2}$ in. diameter.

A full hook takes three seconds' bending time. It is also equipped with accessories for bending angle loops in one operation on mild steel reinforcement up to 1 in. diameter.

HOOPS & SPIRALS

We supply, at extra cost, an appliance (illustrated here) for use with RAS.40 and ARD.50 models for the bending of hoops and spirals. Bends radii of 11 in. and upwards and to any pitch of spiral.



Our Bending Equipment also includes the ARD.50 model—a double-disc machine for bending bars up to 2 in. diameter. We also supply, at extra cost, formers and backrests for special steel such as "Square Grip," "Twistee," etc., which can be fitted to the ARD.50 and RAS.40 models. Full details are available on request. All machines are available for Sale or Hire.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580.

Telegrams & Cables: Cembelgi, Chatham

ABELSON

POURING SKIPS

for CONCRETE, CEMENT and AGGREGATES



Chains to suit—
4 leg 5/16" M.S.
Weight 18 lbs or 25 lbs.
S.W.L. 16 cwt & 30 cwt.



See us at the Ministry
of Works Building
Plant Exhibition,
Heaton Park, Man-
chester, July 15-20.

Other sizes and types available.

Please write for illustrated leaflet number C.S. 8

ABELSON & CO. (Engineers) LTD., SHELDON, BIRMINGHAM, 26


Phone: Sheldon 2424 (10 lines)


Grams: Abelson, Birmingham

London Office
60/62 CLAPHAM ROAD, LONDON, S.W.9
Telephone: RELiance 7081

Manchester Office
100 OXFORD ROAD, MANCHESTER, 13
Telephone: Manchester ARDwick 1328

SIZE	CAPACITY CU. FT.		
	10	14	9
Height 'A'	3' 9"	Bottom 3' 6" Side 3' 8"	3' 3"
Length 'B'	3' 10"	3' 3"	3' 3"
Width 'C'	3' 10"	3' 3"	2' 5"
Weight 'D'	3½ cwt.	3 cwt.	2 cwt.
Overall Height inc. Chains 'E'	7' 6"	7' 4"	7' 2"
Construction 'H'	⅝" M.S. Plate 2" x ¾" A/Iron		
Stand 'J1' x 'J2'	2" A/Iron 3' 0" x 2' 8"	2" A/Iron 2' 8" x 2' 4"	2" A/Iron 3' 0" x 2' 2"
'F1' x 'F2'	Discharge Gate		
Bottom	1' 10" x 10"	1' 6" x 11"	1' 5" x 11"
Side	1' 10" x 11"	1' 6" x 8"	1' 6" x 8"
'K'	Price Ex-Works C.W. Chains		
Bottom	£50-0-0	£47-0-0	£35-0-0
Side	£55-0-0	£50-0-0	£37-0-0






**with WEYROC in your store
you can do so many jobs
so much quicker !**

Weyroc Man-Made Timber is the board you know will do everything you ask of it. Space-filling or load-bearing, these 8' x 4' boards $\frac{1}{2}$ " or $\frac{3}{4}$ " thick, are absolutely faultless, will never let you down. Natural Weyroc takes all normal finishes readily—and for extra decorative speed there is the paper-surfaced grade.

Keep some Weyroc in store. It's the board with all the answers for every job. Weyroc—one of the world's greatest man-made materials.



THE AIRSCREW COMPANY & JICWOOD LTD. • WEYBRIDGE • SURREY

Telephone : Weybridge 2242-6



PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361

*For faster placing
and better concrete
use the*



HUMDINGER

IMMERSION VIBRATOR

AVAILABLE WITH GRINDING ATTACHMENTS



Here is an immersion vibrator that will cut your concrete-placing costs in a half-dozen ways. High vibrating frequencies of up to 12,000 r.p.m. give stronger concrete and speed up placing—and you can strike shuttering sooner. At the same time, the 'Humdinger' flexible shafts operate at **QUARTER SPEED.**

And this means longer life and less maintenance—the drives just keep on running week after week.

Plant records prove that contractors and civil engineers are changing to 'Humdinger' after seeing the difference they can make in concrete placing. Prove it for yourself by using one on your next vibrating job. You can have a 'Humdinger' on trial or hire (with option).



PETROL AND ELECTRIC MODELS AVAILABLE

ACE MACHINERY LIMITED

VIBRATOR DEPT., PORDEN ROAD, BRIXTON, LONDON, S.W.2 Telephone: BR1xton 3293 (9 lines)

Buy  and you buy **RELIABILITY**

BUCKLESBURY HOUSE TO STAND ON 3,500 BORED PILES



This important Office Building in the City of London, 17 storeys high including the basement floors, is supported on Cementation Bored Piles. Approximately 3,500 were constructed well within the contract time despite the fact that delays were unavoidably occasioned by the deliberations on the fate of the Mithras Temple discovered on the site and other major difficulties inevitable on such a large site.

The construction of a surrounding wall to retain the adjoining Queen Victoria Street, Cannon Street and Bucklersbury, was greatly facilitated by the use of our bored piles.

The close proximity of important buildings, including the Mansion House, and services such as the Underground Railway, made it necessary to reduce noise, vibration, etc., to an absolute minimum.




BENTLEY WORKS, DONCASTER. Telephone : Doncaster 54177-8-9

London Office : 20 Albert Embankment, S.E.11. Tel. : RELiance 7654

APPROVED FOR SITE TESTING on all Government Departments' Contracts



4" PRESS AND MOULD



6" PRESS AND MOULD

in use all over the world

MILBANK-WELLS HYDRAULIC PRESS AND CUBE MOULDS FOR CONCRETE TESTING

Presses and Moulds in the 2 sizes for Testing 4 in. and 6 in. cubes
up to 16,000 lb. per square inch, complying with B.S. 1881.

MILBANK FLOORS LTD.

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX.

Telephone: Earls Colne 410

Manufactured for us by Horner & Wells, Ltd., Engineers, Chelmsford, Essex.

ROLLER and ROCKER BEARINGS for CONCRETE BRIDGES and STRUCTURES



Consulting Engineer:
Donovan H. Lee, B.Sc. (Eng.), M.I.C.E.

All types can be supplied, including multiple roller bearings with rockers, single roller bearings, rocker bearings and hemispherical bearings.

JOSEPH WESTWOOD & CO. LTD.

Bridge and Constructional Engineers, Manufacturers of Mechanical Grabs, Pressed Steel Troughing and Sheet Metal Equipment. Steel Stock Holders.

NAPIER YARD, MILLWALL, LONDON, E.14

AIDS TO CONCRETE FORMWORK

For Double-sided walls

The Rawltie consists of two or more straight high tensile steel rods welded at either end to a steel coiled socket and is used in conjunction with bolts having a special thread which prevents any ingress of concrete between bolt and socket. The bolts are thus easily removable and can be used over and over again.

Rawlties are made in lengths of 3 in. to 33 in., going up in stages of 3 in., i.e., 3 in., 6 in., 9 in., 12 in., and so on. Special sizes can be made to order. In combination with the associated Hardwood cones which are made in lengths of 1 in., 1½ in., 2 in. and 2½ in. any thickness of wall can be constructed from 5 in. upwards.

Rawlties are for use where shuttering is erected on both sides of a wall.

STANDARD
RAWLTIE



RAWLTIE WITH BAFFLE
PLATE TO PREVENT
SEEPAGE OF WATER



STANDARD
RAWLOOP. DOUBLE
LOOPS CAN BE MADE

For Single-sided walls

The Rawloop consists of a looped steel rod with a single coiled socket welded between the free ends. It is twisted so that the plane of the steel bar is at an angle to present a greater resistance to withdrawal from partially set concrete.

They are made in four sizes; 4 in. and 6 in. lengths for use with ½ in. bolts, and 6 in. and 9 in. lengths for use with ¾ in. bolts.

Rawloops are for use where shuttering is erected on one side only of a wall, e.g., reinforcing walls, plinths or walls with a taper formation such as trapezoidal walls. Special sizes can be made to order.

For Overhead work

The Rawlhanger is similar in construction to the Rawltie except that the rod is shaped to enable a concrete casing to be provided in-situ around a horizontal beam, girder or joist by supporting the formwork in the required position.

Cones are not required as the formwork is normally tightened up against a precast concrete block imposed between the base of the beam and the formwork to provide the necessary cover.

The coiled sockets left in the beam can subsequently be used as anchorage points for the fixing of any desired permanent fittings.

STANDARD
RAWLHANGER




B563

If you are interested in the possible use of one or more of these Rawplug Devices may we suggest that you ask for our Technical Representative to call and discuss the details of the job with you. You will not incur the slightest obligation, and you may learn something to your benefit.



THE RAWLPLUG COMPANY LTD.
CROMWELL ROAD · LONDON · S.W.7



Reinforced Precast
Concrete Units

CONCRETE SERVICES

LIMITED

HEAD OFFICE:
BLUE BRIDGE LANE
YORK

WORKS:
OUSEACRES, BOROUGHBIDGE ROAD
YORK

TELEPHONE: YORK 24728 (6 lines)



JAMES WAIT
AND THE KETTLE —

Taking thought...

The deep contemplation of great minds may seem to have little in common with the man of action—yet all practical projects have their origin in the mind of man, and great modern engineering achievements must be based on profound scientific thought.

Large modern structures—dams, bridges, causeways and the like—require the up-to-date and efficient designs, methods and materials implicit in the use of prestressed concrete.

The thoughtful engineer will demand the finest materials, including

HIGH-TENSILE STEEL WIRE

developed specially by British Ropes Limited


FOR PRESTRESSED CONCRETE

*Our New Publication
"WIRE FOR
PRESTRESSED
CONCRETE" is
now available. Copies
will be sent, on request,
to members of
interested firms.*

BRITISH ROPES LIMITED

WIRE SALES HEAD OFFICE — **DONCASTER**

TELEPHONE: DONCASTER 4010



HOLST
3 CO LTD

44 CLARENDON ROAD, WATFORD

DESIGN & CONSTRUCTION IN REINFORCED CONCRETE

Branches : BIRMINGHAM, MANCHESTER, LEEDS, DURHAM, EDINBURGH, CARDIFF



Concrete Facts About Mark II Formwork

Speed and efficiency are essential when you build in reinforced concrete. The Kwikform Mark II Formwork system makes it easy for you to use the most advanced techniques in concrete placing. Mark II needs no external support and will take pours of up to 6 ft. of rapidly deposited concrete—greater pours with the use of the 10'0" long Heavy Duty Aligner. Designed to give the fastest possible speed in fixing and striking, and with only four basic components, the equipment can be handled rapidly and efficiently by unskilled labour. Mark II gives a superior finish. It is adaptable to any dimension—for slab floors, columns, beams and walls. All Kwikform equipment is available on sale or hire terms.

Users of the Mark II system gain the following outstanding advantages:

MATCHLESS in speed of erection and striking.


SIMPLE—only four basic components.

ADAPTABLE—designed to meet the widest possible range of uses and to permit the simple use of timber without impairing the speed of erection.

REVOLUTIONARY aligning device which completely eliminates the use of cones or distance pieces.


ECONOMICAL—fewer loose parts than any other system, with the consequent saving in site losses.

ELIMINATES the use of tube and fittings. Wallings built-in, giving a further reduction in potential site losses.



KWIKFORM

HEAD OFFICE: WATERLOO ROAD, BIRMINGHAM 25. ACOCKS GREEN 1152
LONDON OFFICE: 46, VICTORIA STREET, S.W.1. VICTORIA 8915 & 9896



Tall buildings at high speed at low cost. Wates have the plant, the organisation and the know-how. Add to this, early collaboration with the owner, his architect and his engineer, and the building goes up on time and within the budget. Quick completion means earlier revenue.

Ideas become concrete when

WATES BUILD

WATES LTD *Building & Civil Engineering Contractors*
HEAD OFFICES · 1258/1260 LONDON ROAD · S.W.16 · Telephone: POLLARDS 5000
LONDON DUBLIN NEW YORK

STABILITY

WIRE

for prestressed concrete

RYLANDS BROTHERS LIMITED
of Warrington

A. E. FARR LTD

*have been carrying out
reinforced concrete work
for over half a century*




This long and unique experience has included the construction of many hundreds of all types of industrial and residential structures, bridges, reservoirs, water towers, sewage works, sea defence works, piling, and foundations. A recent contract is the reservoir illustrated above constructed by us for the Mid-Northamptonshire Water Board. Engineers : Messrs. L. G. Mouchel & Partners, Ltd.

Head Office : WESTBURY, WILTS.

London Office : 2 Victoria Street, London, S.W.1

Modern Methods need Modern Materials ...



LISSAPOL N

non-ionic surface-active agent for improved workability of concrete.

APHROSOL FC

foaming agent, valuable in production of aerated concrete blocks and roofing screeds.

MELGAN A

outstanding and economical plasticiser for cement mortars.


ADHEVIA T. ADHEVIA AQ

adhesion assistants for preventing wet weather stripping of surface-dressed roads.



Full information on request:


IMPERIAL CHEMICAL INDUSTRIES LIMITED LONDON S.W.1




OVER 3,000,000

in use by large and small contractors in all
parts of the world are the best proof that
for consistent quality and reliability you can't beat

ACROW PROPS



ACROW (ENGINEERS) LTD., SOUTH WHARF, PADDINGTON, LONDON, W.2 • AMBassador 3456 (20 lines)



*Softening and descaling line
at Shepcote Lane Rolling
Mills, Ltd.*

In this age of atomic energy and jet propulsion the production of heat-resisting steels is of vital importance. Firth-Vickers Stainless Steels Ltd., and their associated companies, are leading producers and recently extended their rolling mills at Sheffield.

Very heavy equipment was needed and thus close attention had to be paid to the concrete base. No. 1 METALLIC LIQUID was specially chosen for incorporating in the mass concrete and in the floor toppings to ensure a dense waterproof and dustless surface.



LILLINGTON'S No. 1 Metallic Liquid has been recognised for nearly 50 years as the only guaranteed proofer that :

Contractors : W. G. Robson, Ltd., Sheffield

- | | | |
|------------------|--------------|-------------------|
| *WATERPROOFS | *DUSTPROOFS | *RAPID HARDENS |
| *ACCELERATES SET | *PLASTICISES | *AIDS WORKABILITY |

From **5/-** per gallon

Special prices for large contracts

For complete details, write for booklet 56

Lillington's
NO. 1 METALLIC LIQUID

GEORGE LILLINGTON & CO. LTD.
WILLOW LANE, MITCHAM, SURREY

Telephone : Mitcham 1066

For Scotland : 42 High Street, Greenock.

Tel. Greenock 20175




shell roof
construction

RICE
& SON LTD

CONTRACTORS FOR
REINFORCED CONCRETE

LONDON BRIGHTON MARGATE SOUTHAMPTON

WHITEHEAD'S REINFORCING BARS



.....

have been regularly used

.....

by leading Contractors for

.....

reinforced concrete work

.....

since 1903

.....

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL have been used include some of the largest and most important in the country.

We can supply bars bent to shape, hooked, etc.,
in accordance with Contractors' requirements,
at reasonable charges.

THE

WHITEHEAD IRON & STEEL CO. LTD.

NEWPORT

Tel. No. NEWPORT 65401 (PBX)

MON


LONDON OFFICE: Steel House, Tothill Street, S.W.1. Telephone: Whitehall 2984.

BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412-3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 3172.

GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes for Compression Test B.S. 12/1947, B.S. 915/1947, B.S. 146/1947, B.S. 1370/1947. New type automatic control—optional. The vibrator illustrated in the B.S. was built in our works.

The "CAPCO" range of concrete testing apparatus also includes Cube Moulds; Slump Cones; Tensile, Vicat, and Cylindrical Moulds; Tile Abrasion Machines; Compacting Factor Apparatus.

Full details on request.

CAPCO (SALES), LTD.

(Sole Agents for all "Capco" Products)

BEACONSFIELD ROAD, LONDON, N.W.10

Telephone: WILLESDEN 0067-8

Cables: CAPLINKO, LONDON



**PIN YOUR FAITH
TO THE TESTED
BRAND.**

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**


THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10

'Grams: "Grease."

maximum floor space for reinforced concrete industrial structures



77,000 sq. ft. floor area with 16 internal columns

is the space available for this warehouse, with an overall size of 352 ft. by 220 ft., constructed by us for the International Harvester Co. of Gt. Britain Ltd. The precast concrete frames were designed, manufactured and erected by Scotcon.

Architects: Messrs. T. H. Johnson & Son, Doncaster.

***The* SCOTTISH CONSTRUCTION CO. LTD.**

**REINFORCED CONCRETE ENGINEERS
AND CONTRACTORS
PRECAST CONCRETE MANUFACTURERS**

SIGHTHILL INDUSTRIAL ESTATE

EDINBURGH 11

HISTORICAL HYPOTHESIS NUMBER 2

John Loudon MacAdam

**got below
the surface
of things**

...by realizing the importance of a hard,
long wearing surface for the roads of his day if they were to cope
effectively with the ever growing volume of traffic

How glad he would have been to use present day concrete cured with
SISALKRAFT Blankets. Their toughness and ease of handling simplify
and speed up road making; a safeguard against winter frosts and
assured curing in summer heat.

He would have marvelled, too, at the strength of Subsoil grade
SISALKRAFT which takes such good care of the underside of concrete,
reducing sub-grade friction, ensuring maximum
strength and protection from impurities.

SISALKRAFT

1857-1957

Please ask for information and samples.

J.H. SANKEY & SON. LTD.

Sole Distributors for BRITISH SISALKRAFT Ltd.

ESSEX WORKS, RIPPLE ROAD, BARKING, ESSEX

Phone: RIPpleway 3055

Grams: BRickwork, Barking

TRIANCO TELESCOPIC **CENTERS**

**THE ORIGINAL TELESCOPIC
SHUTTERING**
used by
LEADING CONTRACTORS

Spans from 2' 10½" to 16' 6" at competitive prices.

Speedy to erect and dismantle.

Simple to handle—no skilled labour required.

Safe to use—combined with light weight.

Saving of Timber.

The lightness in weight of these Centers in no way impairs their strength owing to the triangular design, which feature provides ample strength and at the same time facilitates handling on site.

An efficient and economical shuttering for hollow block and suspended reinforced concrete floors.

Write for particulars to:

TRIANCO LIMITED.


TRIANCO LTD., Imber Court, EAST MOLESEY, Surrey
Telephone: EMBrook 3300 (4 lines)
Telegrams: TRIANCO, EAST MOLESEY



READY-MIXED CONCRETE from

our plants at
NOTTINGHAM
AND
MANSFIELD

can be delivered in any quantity—
large or small—to contracts in the
district shown here.



TRENT GRAVELS LTD.

To meet the ever-increasing demand for ready-mixed concrete, we now operate a new and up-to-date plant at Mansfield which, with our plant at Nottingham, affords greater opportunities for Contractors to take full advantage of ready-mixed concrete to speed up construction work and reduce concreting costs and labour requirements on the site, for all contracts in the district shown above. We can supply ready-mixed concrete graded to any specification, with a delivery service which is guaranteed to comply with your concreting schedules. Include our name on your list for future inquiries. Full details are available on request.

ATTENBOROUGH, NOTTS.

AND KING JOHN CHAMBERS, BRIDLESMITH GATE, NOTTINGHAM

TELEPHONE : BEESTON 25-4255/6

TELEPHONE : 40557



THORESBY COAL PREPARATION PLANT (N.C.B.)

**CONTRACTS RECENTLY CARRIED OUT BY
US IN REINFORCED CONCRETE INCLUDE ...**

**LEONARD
FAIRCLOUGH
LTD**

Colliery Blending Bunkers.
Weighbridge Foundations.
Washery and Coal Preparation
Plants. Power House and Wind-
ing Engine Houses. (N.C.B.)
Roadways. Road, Railway and
Canal Bridges. Warehouses.
Factories. Sewage Scheme.

**CONTRACTORS FOR REINFORCED CONCRETE,
CIVIL ENGINEERING AND BUILDING WORK**

HEAD OFFICE: Adlington, Lancs. Telephone: Adlington 264/5/6.

LONDON OFFICE: Gordon House Road, N.W.5.

Telephone: Gulliver 7309 & 7408.


MANCHESTER OFFICE: 573 Chester Road, Manchester 16.

SINEX

PNEUMATIC

THE VIBRATOR HEAD
THAT NEEDS
NO MAINTENANCE

TURBO VIBRATOR



This easily-handled pneumatic turbo-vibrator has a frequency range of 10,000 to 18,000 per minute. Its vibrating head, illustrated on the left, has been specially designed to eliminate maintenance costs. The head can be supplied in sizes from 1 $\frac{3}{8}$ in. diameter to 4 in. diameter, in lengths from 19 $\frac{1}{2}$ in. to 24 in. This new type of vibrator represents an important step in the development of modern equipment for concrete work and will conform to all the requirements for the highest efficiency with the lowest operating costs.

The range of SINEX VIBRATING EQUIPMENT also includes electric vibrators for external and vibrating tables. Full details of the complete range are available on request.

SINEX ENGINEERING CO. LTD and CONCRETE VIBRATION LTD

12 ROCHESTER ROW, WESTMINSTER, S.W.1

Telephone : VIC. 7503-4

SOLE SALES CONCESSIONAIRES : WARSOP POWER TOOLS LIMITED

77, 79, 81, 83, 85, 87, 89, 91, 93, 95, 97, 99, 101, 103, 105, 107, 109, 111, 113, 115, 117, 119, 121, 123, 125, 127, 129, 131, 133, 135, 137, 139, 141, 143, 145, 147, 149, 151, 153, 155, 157, 159, 161, 163, 165, 167, 169, 171, 173, 175, 177, 179, 181, 183, 185, 187, 189, 191, 193, 195, 197, 199, 201, 203, 205, 207, 209, 211, 213, 215, 217, 219, 221, 223, 225, 227, 229, 231, 233, 235, 237, 239, 241, 243, 245, 247, 249, 251, 253, 255, 257, 259, 261, 263, 265, 267, 269, 271, 273, 275, 277, 279, 281, 283, 285, 287, 289, 291, 293, 295, 297, 299, 301, 303, 305, 307, 309, 311, 313, 315, 317, 319, 321, 323, 325, 327, 329, 331, 333, 335, 337, 339, 341, 343, 345, 347, 349, 351, 353, 355, 357, 359, 361, 363, 365, 367, 369, 371, 373, 375, 377, 379, 381, 383, 385, 387, 389, 391, 393, 395, 397, 399, 401, 403, 405, 407, 409, 411, 413, 415, 417, 419, 421, 423, 425, 427, 429, 431, 433, 435, 437, 439, 441, 443, 445, 447, 449, 451, 453, 455, 457, 459, 461, 463, 465, 467, 469, 471, 473, 475, 477, 479, 481, 483, 485, 487, 489, 491, 493, 495, 497, 499, 501, 503, 505, 507, 509, 511, 513, 515, 517, 519, 521, 523, 525, 527, 529, 531, 533, 535, 537, 539, 541, 543, 545, 547, 549, 551, 553, 555, 557, 559, 561, 563, 565, 567, 569, 571, 573, 575, 577, 579, 581, 583, 585, 587, 589, 591, 593, 595, 597, 599, 601, 603, 605, 607, 609, 611, 613, 615, 617, 619, 621, 623, 625, 627, 629, 631, 633, 635, 637, 639, 641, 643, 645, 647, 649, 651, 653, 655, 657, 659, 661, 663, 665, 667, 669, 671, 673, 675, 677, 679, 681, 683, 685, 687, 689, 691, 693, 695, 697, 699, 701, 703, 705, 707, 709, 711, 713, 715, 717, 719, 721, 723, 725, 727, 729, 731, 733, 735, 737, 739, 741, 743, 745, 747, 749, 751, 753, 755, 757, 759, 761, 763, 765, 767, 769, 771, 773, 775, 777, 779, 781, 783, 785, 787, 789, 791, 793, 795, 797, 799, 801, 803, 805, 807, 809, 811, 813, 815, 817, 819, 821, 823, 825, 827, 829, 831, 833, 835, 837, 839, 841, 843, 845, 847, 849, 851, 853, 855, 857, 859, 861, 863, 865, 867, 869, 871, 873, 875, 877, 879, 881, 883, 885, 887, 889, 891, 893, 895, 897, 899, 901, 903, 905, 907, 909, 911, 913, 915, 917, 919, 921, 923, 925, 927, 929, 931, 933, 935, 937, 939, 941, 943, 945, 947, 949, 951, 953, 955, 957, 959, 961, 963, 965, 967, 969, 971, 973, 975, 977, 979, 981, 983, 985, 987, 989, 991, 993, 995, 997, 999, 1001, 1003, 1005, 1007, 1009, 1011, 1013, 1015, 1017, 1019, 1021, 1023, 1025, 1027, 1029, 1031, 1033, 1035, 1037, 1039, 1041, 1043, 1045, 1047, 1049, 1051, 1053, 1055, 1057, 1059, 1061, 1063, 1065, 1067, 1069, 1071, 1073, 1075, 1077, 1079, 1081, 1083, 1085, 1087, 1089, 1091, 1093, 1095, 1097, 1099, 1101, 1103, 1105, 1107, 1109, 1111, 1113, 1115, 1117, 1119, 1121, 1123, 1125, 1127, 1129, 1131, 1133, 1135, 1137, 1139, 1141, 1143, 1145, 1147, 1149, 1151, 1153, 1155, 1157, 1159, 1161, 1163, 1165, 1167, 1169, 1171, 1173, 1175, 1177, 1179, 1181, 1183, 1185, 1187, 1189, 1191, 1193, 1195, 1197, 1199, 1201, 1203, 1205, 1207, 1209, 1211, 1213, 1215, 1217, 1219, 1221, 1223, 1225, 1227, 1229, 1231, 1233, 1235, 1237, 1239, 1241, 1243, 1245, 1247, 1249, 1251, 1253, 1255, 1257, 1259, 1261, 1263, 1265, 1267, 1269, 1271, 1273, 1275, 1277, 1279, 1281, 1283, 1285, 1287, 1289, 1291, 1293, 1295, 1297, 1299, 1301, 1303, 1305, 1307, 1309, 1311, 1313, 1315, 1317, 1319, 1321, 1323, 1325, 1327, 1329, 1331, 1333, 1335, 1337, 1339, 1341, 1343, 1345, 1347, 1349, 1351, 1353, 1355, 1357, 1359, 1361, 1363, 1365, 1367, 1369, 1371, 1373, 1375, 1377, 1379, 1381, 1383, 1385, 1387, 1389, 1391, 1393, 1395, 1397, 1399, 1401, 1403, 1405, 1407, 1409, 1411, 1413, 1415, 1417, 1419, 1421, 1423, 1425, 1427, 1429, 1431, 1433, 1435, 1437, 1439, 1441, 1443, 1445, 1447, 1449, 1451, 1453, 1455, 1457, 1459, 1461, 1463, 1465, 1467, 1469, 1471, 1473, 1475, 1477, 1479, 1481, 1483, 1485, 1487, 1489, 1491, 1493, 1495, 1497, 1499, 1501, 1503, 1505, 1507, 1509, 1511, 1513, 1515, 1517, 1519, 1521, 1523, 1525, 1527, 1529, 1531, 1533, 1535, 1537, 1539, 1541, 1543, 1545, 1547, 1549, 1551, 1553, 1555, 1557, 1559, 1561, 1563, 1565, 1567, 1569, 1571, 1573, 1575, 1577, 1579, 1581, 1583, 1585, 1587, 1589, 1591, 1593, 1595, 1597, 1599, 1601, 1603, 1605, 1607, 1609, 1611, 1613, 1615, 1617, 1619, 1621, 1623, 1625, 1627, 1629, 1631, 1633, 1635, 1637, 1639, 1641, 1643, 1645, 1647, 1649, 1651, 1653, 1655, 1657, 1659, 1661, 1663, 1665, 1667, 1669, 1671, 1673, 1675, 1677, 1679, 1681, 1683, 1685, 1687, 1689, 1691, 1693, 1695, 1697, 1699, 1701, 1703, 1705, 1707, 1709, 1711, 1713, 1715, 1717, 1719, 1721, 1723, 1725, 1727, 1729, 1731, 1733, 1735, 1737, 1739, 1741, 1743, 1745, 1747, 1749, 1751, 1753, 1755, 1757, 1759, 1761, 1763, 1765, 1767, 1769, 1771, 1773, 1775, 1777, 1779, 1781, 1783, 1785, 1787, 1789, 1791, 1793, 1795, 1797, 1799, 1801, 1803, 1805, 1807, 1809, 1811, 1813, 1815, 1817, 1819, 1821, 1823, 1825, 1827, 1829, 1831, 1833, 1835, 1837, 1839, 1841, 1843, 1845, 1847, 1849, 1851, 1853, 1855, 1857, 1859, 1861, 1863, 1865, 1867, 1869, 1871, 1873, 1875, 1877, 1879, 1881, 1883, 1885, 1887, 1889, 1891, 1893, 1895, 1897, 1899, 1901, 1903, 1905, 1907, 1909, 1911, 1913, 1915, 1917, 1919, 1921, 1923, 1925, 1927, 1929, 1931, 1933, 1935, 1937, 1939, 1941, 1943, 1945, 1947, 1949, 1951, 1953, 1955, 1957, 1959, 1961, 1963, 1965, 1967, 1969, 1971, 1973, 1975, 1977, 1979, 1981, 1983, 1985, 1987, 1989, 1991, 1993, 1995, 1997, 1999, 2001, 2003, 2005, 2007, 2009, 2011, 2013, 2015, 2017, 2019, 2021, 2023, 2025, 2027, 2029, 2031, 2033, 2035, 2037, 2039, 2041, 2043, 2045, 2047, 2049, 2051, 2053, 2055, 2057, 2059, 2061, 2063, 2065, 2067, 2069, 2071, 2073, 2075, 2077, 2079, 2081, 2083, 2085, 2087, 2089, 2091, 2093, 2095, 2097, 2099, 2101, 2103, 2105, 2107, 2109, 2111, 2113, 2115, 2117, 2119, 2121, 2123, 2125, 2127, 2129, 2131, 2133, 2135, 2137, 2139, 2141, 2143, 2145, 2147, 2149, 2151, 2153, 2155, 2157, 2159, 2161, 2163, 2165, 2167, 2169, 2171, 2173, 2175, 2177, 2179, 2181, 2183, 2185, 2187, 2189, 2191, 2193, 2195, 2197, 2199, 2201, 2203, 2205, 2207, 2209, 2211, 2213, 2215, 2217, 2219, 2221, 2223, 2225, 2227, 2229, 2231, 2233, 2235, 2237, 2239, 2241, 2243, 2245, 2247, 2249, 2251, 2253, 2255, 2257, 2259, 2261, 2263, 2265, 2267, 2269, 2271, 2273, 2275, 2277, 2279, 2281, 2283, 2285, 2287, 2289, 2291, 2293, 2295, 2297, 2299, 2301, 2303, 2305, 2307, 2309, 2311, 2313, 2315, 2317, 2319, 2321, 2323, 2325, 2327, 2329, 2331, 2333, 2335, 2337, 2339, 2341, 2343, 2345, 2347, 2349, 2351, 2353, 2355, 2357, 2359, 2361, 2363, 2365, 2367, 2369, 2371, 2373, 2375, 2377, 2379, 2381, 2383, 2385, 2387, 2389, 2391, 2393, 2395, 2397, 2399, 2401, 2403, 2405, 2407, 2409, 2411, 2413, 2415, 2417, 2419, 2421, 2423, 2425, 2427, 2429, 2431, 2433, 2435, 2437, 2439, 2441, 2443, 2445, 2447, 2449, 2451, 2453, 2455, 2457, 2459, 2461, 2463, 2465, 2467, 2469, 2471, 2473, 2475, 2477, 2479, 2481, 2483, 2485, 2487, 2489, 2491, 2493, 2495, 2497, 2499, 2501, 2503, 2505, 2507, 2509, 2511, 2513, 2515, 2517, 2519, 2521, 2523, 2525, 2527, 2529, 2531, 2533, 2535, 2537, 2539, 2541, 2543, 2545, 2547, 2549, 2551, 2553, 2555, 2557, 2559, 2561, 2563, 2565, 2567, 2569, 2571, 2573, 2575, 2577, 2579, 2581, 2583, 2585, 2587, 2589, 2591, 2593, 2595, 2597, 2599, 2601, 2603, 2605, 2607, 2609, 2611, 2613, 2615, 2617, 2619, 2621, 2623, 2625, 2627, 2629, 2631, 2633, 2635, 2637, 2639, 2641, 2643, 2645, 2647, 2649, 2651, 2653, 2655, 2657, 2659, 2661, 2663, 2665, 2667, 2669, 2671, 2673, 2675, 2677, 2679, 2681, 2683, 2685, 2687, 2689, 2691, 2693, 2695, 2697, 2699, 2701, 2703, 2705, 2707, 2709, 2711, 2713, 2715, 2717, 2719, 2721, 2723, 2725, 2727, 2729, 2731, 2733, 2735, 2737, 2739, 2741, 2743, 2745, 2747, 2749, 2751, 2753, 2755, 2757, 2759, 2761, 2763, 2765, 2767, 2769, 2771, 2773, 2775, 2777, 2779, 2781, 2783, 2785, 2787, 2789, 2791, 2793, 2795, 2797, 2799, 2801, 2803, 2805, 2807, 2809, 2811, 2813, 2815, 2817, 2819, 2821, 2823, 2825, 2827, 2829, 2831, 2833, 2835, 2837, 2839, 2841, 2843, 2845, 2847, 2849, 2851, 2853, 2855, 2857, 2859, 2861, 2863, 2865, 2867, 2869, 2871, 2873, 2875, 2877, 2879, 2881, 2883, 2885, 2887, 2889, 2891, 2893, 2895, 2897, 2899, 2901, 2903, 2905, 2907, 2909, 2911, 2913, 2915, 2917, 2919, 2921, 2923, 2925, 2927, 2929, 2931, 2933, 2935, 2937, 2939, 2941, 2943, 2945, 2947, 2949, 2951, 2953, 2955, 2957, 2959, 2961, 2963, 2965, 2967, 2969, 2971, 2973, 2975, 2977, 2979, 2981, 2983, 2985, 2987, 2989, 2991, 2993, 2995, 2997, 2999, 3001, 3003, 3005, 3007, 3009, 3011, 3013, 3015, 3017, 3019, 3021, 3023, 3025, 3027, 3029, 3031, 3033, 3035, 3037, 3039, 3041, 3043, 3045, 3047, 3049, 3051, 3053, 3055, 3057, 3059, 3061, 3063, 3065, 3067, 3069, 3071, 3073, 3075, 3077, 3079, 3081, 3083, 3085, 3087, 3089, 3091, 3093, 3095, 3097, 3099, 3101, 3103, 3105, 3107, 3109, 3111, 3113, 3115, 3117, 3119, 3121, 3123, 3125, 3127, 3129, 3131, 3133, 3135, 3137, 3139, 3141, 3143, 3145, 3147, 3149, 3151, 3153, 3155, 3157, 3159, 3161, 3163, 3165, 3167, 3169, 3171, 3173, 3175, 3177, 3179, 3181, 3183, 3185, 3187, 3189, 3191, 3193, 3195, 3197, 3199, 3201, 3203, 3205, 3207, 3209, 3211, 3213, 3215, 3217, 3219, 3221, 3223, 3225, 3227, 3229, 3231, 3233, 3235, 3237, 3239, 3241, 3243, 3245, 3247, 3249, 3251, 3253, 3255, 3257, 3259, 3261, 3263, 3265, 3267, 3269, 3271, 3273, 3275, 3277, 3279, 3281, 3283, 3285, 3287, 3289, 3291, 3293, 3295, 3297, 3299, 3301, 3303, 3305, 3307, 3309, 3311, 3313, 3315, 3317, 3319, 3321, 3323, 3325, 3327, 3329, 3331, 3333, 3335, 3337, 3339, 3341, 3343, 3345, 3347, 3349, 3351, 3353, 3355, 3357, 3359, 3361, 3363, 3365, 3367, 3369, 3371, 3373, 3375, 3377, 3379, 3381, 3383, 3385, 3387, 3389, 3391, 3393, 3395, 3397, 3399, 3401, 3403, 3405, 3407, 3409, 3411, 3413, 3415, 3417, 3419, 3421, 3423, 3425, 3427, 3429, 3431, 3433, 3435, 3437, 3439, 3441, 3443, 3445, 3447, 3449, 3451, 3453, 3455, 3457, 3459, 3461, 3463, 3465, 3467, 3469, 3471, 3473, 3475, 3477, 3479, 3481, 3483, 3485, 3487, 3489, 3491, 3493, 3495, 3497, 3499, 3501, 3503, 3505, 3507, 3509, 3511, 3513, 3515, 3517, 3519, 3521, 3523, 3525, 3527, 3529, 3531, 3533, 3535, 3537, 3539, 3541, 3543, 3545, 3547, 3549, 3551, 3553, 3555, 3557, 3559, 3561, 3563, 3565, 3567, 3569, 3571, 3573, 3575, 3577, 3579, 3581, 3583, 3585, 3587, 3589, 3591, 3593, 3595, 3597, 3599, 3601, 3603, 3605, 3607, 3609, 3611, 3613, 3615, 3617, 3619, 3621, 3623, 3625, 3627, 3629, 3631, 3633, 3635, 3637, 3639, 3641, 3643, 3645, 3647, 3649, 3651, 3653, 3655, 3657, 3659, 3661, 3663, 3665, 3667, 3669, 3671, 3673, 3675, 3677, 3679, 3681, 3683, 3685, 3687, 3689, 3691, 3693, 3695, 3697, 3699, 3701, 3703, 3705, 3707, 3709, 3711, 3713, 3715, 3717, 3719, 3721, 3723, 3725, 3727, 3729, 3731, 3733, 3735, 3737, 3739, 3741, 3743, 3745, 3747, 3749, 3751, 3753, 3755, 3757, 3759, 3761, 3763, 3765, 3767, 3769, 3771, 3773, 3775, 3777, 3779, 3781, 3783, 3785, 3787, 3789, 3791, 3793, 3795, 3797, 3799, 3801, 3803, 3805, 3807, 3809, 3811, 3813, 3815, 3817, 3819, 3821, 3823, 3825, 3827, 3829, 3831, 3833, 3835, 3837, 3839, 3841, 3843, 3845, 3847, 3849, 3851, 3853, 3855, 3857, 3859, 3861, 3863, 3865, 3867, 3869, 3871, 3873, 3875, 3877, 3879, 3881, 3883, 3885, 3887, 3889, 3891, 3893, 3895, 3897, 3899, 3901, 3903, 3905, 3907, 3909, 3911, 3913, 3915, 3917, 3919, 3921, 3923, 3925, 3927, 3929, 3931, 3933, 3935, 3937, 3939, 3941, 3943, 3945, 3947, 3949, 3951, 3953, 3955, 3957, 3959, 3961, 3963, 3965, 3967, 3969, 3971, 3973, 3975, 3977, 3979, 3981, 3983, 3985, 3987, 3989, 3991, 3993, 3995, 3997, 3999, 4001, 4003, 4005, 4007, 4009, 4011, 4013, 4015, 4017, 4019, 4021, 4023, 4025, 4027, 4029, 4031, 4033, 4035, 4037, 4039, 4041, 4043, 4045, 4047, 4049, 4051, 4053, 4055, 4057, 4059, 4061, 4063, 4065, 406




... Outstanding products

CHEMICAL
BUILDING
PRODUCTS LTD
Warple Works
Cleveland Road
Hemel Hempstead
Herts

PROLAPIN Liquid Cement Waterproofer
LITHURIN Concrete Floor Hardener
QUICKSOCRETE P. Q. & D. Rapid Hardeners and Setters
WETEXI 'S' Colourless Silicone Impregnation
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
CEBEX 125 Workability Aid for Concrete
LIFTOYL Floor Cleaner and Degreaser
ORKIT & TEKTAM Bituminous Coatings and Compounds
CONCURE Concrete Curing Agent
NITOLUX & ROBRITE Paints

CHEMICAL BUILDING PRODUCTS LTD

Telephone : BOXMOOR 4900 (5 lines)
Telegrams : Prolithu Hemel Hempstead



... why not let Ford solve it for you? They've a pretty range of curves—performance, torque, fuel and B.H.P., covering Petrol and Vaporising Oil Engines from 12 to 58 B.H.P. (Diesel 23 to 52 B.H.P.). All supremely suitable for heavy duty industrial operation—all possessing the manifold advantages of World-wide Ford Service. In fact whenever there's a question of curves ...

— ask the fellows at



All enquiries, please, to your nearest Dealer or to:—

Parts Division. Domestic Industrial Unit Sales Dept. G8

Ford Motor Company Ltd • Avelay Depot • South Ockendon • Romford • Essex • England

Prestressed Concrete Duct Grouting

NORTHAM BRIDGE • SOUTHAMPTON

*Precast Sections Prestressed together by Freyssinet
System and Cable Ducts Colgrouted*



Consulting Engineers:
Rendel, Palmer &
Tritton.

Contractors :
Christiani & Neilsen
Limited.

Mobile Grouting Units with skilled operators are available in the United Kingdom at a fixed daily charge. Upwards of 60 ducts usually grouted per day on site.


Colcrete Equipment is used extensively for the grouting of Post Tensioned Prestressed Concrete Cable and Bar Ducts. Both horizontal and vertical ducts can be filled completely and sealed off under controlled pressures of up to 125 p.s.i. using sanded grout or expansile cement slurry or low water/cement ratio.



**PLANT SOLD
OVERSEAS**

COLCRETE LTD.

GUN LANE • STROOD • KENT • Tel.: Strood 78431-2-3



The traffic rolls...

an ever-increasing load on the country's roads ... only concrete soundly founded can stand up to it. That's why you'll see more and more IBECO used on road construction and repair jobs. It's tough, it improves strength, it lengthens the life of the road and it saves money. We'll be glad to send you samples.



C. Davidson & Sons Ltd.,
Mugiemoss, Aberdeenshire.


WATERPROOF CONCRETING PAPER

HILTON GRAVEL

**SEVEN
PITS**

**250
LORRIES**

**8,000
TONS
PER DAY**



FOR QUALITY & SERVICE

REGULAR DELIVERIES THROUGHOUT

STAFFORDSHIRE • CHESHIRE

DERBYSHIRE • NOTTINGHAMSHIRE

WEST RIDING • LANCASHIRE

SHROPSHIRE • WARWICKSHIRE

LEICESTERSHIRE • RUTLAND

The illustration above shows one of our seven pits equipped with the most modern washing and grading plant for producing concrete aggregates that will satisfy the most exacting requirements for cleanliness and grading to specifications.

**READY
MIXED
CONCRETE**

20 miles radius
MANCHESTER


From our Plant
at
**RICE STREET
MANCHESTER 3**

DEAnsgate 5455


HILTON GRAVEL LIMITED

HEAD OFFICE: HILTON DERBY Tel: ETWALL 422

THE JOHNSON MULTIBRATOR
 High frequency poker type concrete vibrator



DISPENSES WITH FLEXIBLE DRIVE SHAFTS




...up to four vibrators from one power unit

Send for this brochure

The advantage of this Johnson development is obvious on the job. Four pokers can be operated and controlled at distances up to 300 feet from the power unit. The motor actually built into the vibrating poker, gives a frequency of 12,000 V.P.M. Poker diameters are $2\frac{3}{8}$ ", $3\frac{1}{2}$ " and $4\frac{1}{4}$ ". Power is derived from either a Frequency Changer, or Diesel Alternator set. Write for the brochure CC.3/0899.


C. H. JOHNSON (MACHINERY) LTD.
ADSWOOD • STOCKPORT • CHESHIRE

Telephone : STOCKport 2642/5 Telegrams : 'Machinery' Stockport
 London Sales and Service Depot, 38-44 Lower Richmond Rd., S.W.14. Tel : PROspect 7671
 Scottish Sales and Service Depot, 15 St. James Ter., Kilmacolin, Renfrewshire. Tel : Kilmacolin 558



CONCRETE PILING LTD

Specialists in the construction of all forms of reinforced concrete structures and civil engineering projects.



Contractors to :

ADMIRALTY · WAR OFFICE · MINISTRY OF
WORKS · BRITISH ELECTRICITY AUTHORITY
DOCKS AND HARBOUR BOARDS · RIVER &
DRAINAGE AUTHORITY · RAILWAYS AND
INLAND WATERWAYS · MINISTRY OF SUPPLY
SHIPBUILDING & HEAVY ENGINEERING INDUSTRIES



CONCRETE PILING LTD

CIVIL ENGINEERING CONTRACTORS


10 WESTMINSTER PALACE GARDENS ARTILLERY ROW LONDON SW1

PHONE ABBEY 1626/7

P4330

* Shaded portions indicate major areas known chemically and geologically to contain sulphates in the soil. Unshaded portions are not necessarily free from sulphates as local conditions (e.g., back-filled pits, made ground, sites of old chemical works, land contaminated by trade effluent, etc.) must be considered and each site examined accordingly.

DANGER! SULPHATES AT WORK



SULFACRETE

SULPHATE RESISTING CEMENT

GIVES PROVED PROTECTION

It is well known that soluble sulphates present in the soil are liable to cause disintegration of concrete made with ordinary Portland cement. With 'SULFACRETE' Sulphate Resisting Cement, concrete can be made proof against concentrations of sulphates in terms of sulphur trioxide up to 0.5% by weight in ground water and 2.0% by weight in soil or clay.



7 YEAR TESTS. These two concrete cylinders, 12 in. by 6 in., were immersed for seven years in a sodium sulphate solution where the equivalent SO_3 content was 500 parts per 100,000. The left-hand cylinder was made with ordinary Portland Cement, that on the right with 'SULFACRETE' Sulphate Resisting Cement.



Write for full details to:


THE CEMENT MARKETING CO. LTD., Portland House, Tothill St., London, S.W.1.
G. & T. EARLE LTD., HULL.

THE SOUTH WALES PORTLAND CEMENT & LIME CO., LTD., Penarth, Glam.



Maxweld reinforces it

Concrete or brickwork, MAXWELD reinforces it: schools, power stations, bridges, roads, warehouses, factories. *Do you need reinforcements? Call up the MAXWELD man! He'll tell you all about MAXWELD fabric—made to BSS. 1221 Part A, closely controlled for quality from raw material onwards, available for quick delivery anywhere. He'll tell you what type you need, how much you need, and how much it's going to cost you. He's backed by Richard Hill's Design Service, always ready to work out detailed plans and estimates. Call up the MAXWELD man—at Middlesbrough, London, Birmingham, Manchester, Leeds, Bristol and Glasgow.*



Maxweld fabric

Is manufactured by **RICHARD HILL LIMITED** (Established 1868)

Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CRC 3MX

LENSCRETE

GLASS AND FERRO-CONCRETE

for

SHELL ROOF


CONSTRUCTION

LENSCRETE LTD.

66 QUEEN'S CIRCUS

LONDON, S.W.8

TELEPHONE : MACAULAY 1063



Agents in all parts
of the British Isles,
Dominions and Colonies.

GUNITE SPECIALISTS

W.M. MULCASTER

& CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone : Crewe 2265-6.



Tel.: UXBRIDGE
3399

T.P.S. SHUTTER-PLY PAINTS

will make your shuttering and moulds last longer
and save the labour costs of repeated mould oil
applications

*Reduced costs and clean concrete surfaces are always
obtained—wood grain is filled and sealed against water
and alkali—Douglas Fir staining eliminated. Types
for all uses*

TECHNICAL PAINT SERVICES DEPT. C.C.E.
COWLEY MILL ROAD ——— UXBRIDGE ——— MIDDLESEX

the ideal
underlay
and overlay

**CHAPMAN'S
WATERPROOF
CONCRETING
PAPER**

Chapman's Concreting Paper conforms to
British Standards. Deliveries can be made
from stock at short notice. Samples and
prices are available on request.

H. W. CHAPMAN LTD.

THE EMBANKMENT • WELLINGBOROUGH • NORTHANTS

TELEPHONE : WELLINGBOROUGH 2214

Steel Reinforcement

... bent ... bundled ... labelled

Delivered to site ready for fixing •

No loss of time in checking and sort-

ing material • No loss of material

due to prolonged storage on site •

A complete service of
DESIGN, FABRICATION AND FIXING
for all types of Reinforced Concrete
Construction.

T. C. JONES

AND COMPANY LIMITED

REINFORCEMENT ENGINEERS

HEAD OFFICE: WOOD LANE, LONDON, W.12

Telephone: SHEphers Bush 2020

SOUTH WALES OFFICE:

2 PIERHEAD CHAMBERS, BUTE STREET, CARDIFF

Telephone: Cardiff 28786

REINFORCEMENT DEPARTMENT:

17 BUCKINGHAM PALACE GARDENS, LONDON, S.W.1

Telephone: SLOne 5271

WORKS: Shepherds Bush, London. Neasden, Middlesex. Treorchy, Glamorgan

THE
600
GROUP
OF COMPANIES

All reinforcement enquiries please, to: 17 Buckingham Palace Gardens, London, S.W.1

★ TWO SERVICES

**QUALITY
CONCRETE
AGGREGATES**

**STANDARD
CONCRETE
BUILDING
BLOCKS**

**and other concrete
products to your
design and specification**

**available for
all contracts
large or small
in**

BEDFORDSHIRE
LINCOLNSHIRE
LEICESTERSHIRE
DERBYSHIRE
NOTTINGHAMSHIRE
NORTHAMPTONSHIRE
BUCKINGHAMSHIRE

We have excellent facilities for providing a first-class service for those engaged in concrete work in the counties listed above. This service includes the supply of the very best washed and graded aggregates, a delivery service that can always be depended on, and immediate attention to urgent requirements.

We also have large stocks of standard concrete building blocks for building and public works contracts, and can supply concrete products to any design and specification.

Consult

C. A. E. C.

HOWARD LTD.
of BEDFORD

C. A. E. C. HOWARD LTD., ST. JOHN'S WORKS, BEDFORD.

TELEPHONES 4204-6, 5367-9



NEEDLE VIBRATOR

with one-inch
diameter head
for concrete
which is congested
with reinforcement
or prestressing wire

Our range of immersion vibrators also includes the Giant pneumatic vibrator with a 4-in. head, the General-Purpose pneumatic vibrator with a 2½-in. head, and the Lightweight electric vibrator with heads ranging from 1½ in. to 3 in. diameters, which is also available with petrol engine.

COMPACTORS ENGINEERING LTD.


65 EFFRA ROAD,

LONDON, S.W.2

TELEPHONE: BRIXTON 4081-3

This one-inch head pneumatic immersion-vibrator solves all problems in obtaining efficient vibration of thin concrete members and concrete which is congested with reinforcement or prestressing wire. The vibrator will give equal satisfaction for general concrete work, as the 1" dia. head can be interchanged in a few minutes for a more powerful 1½" or 2½" dia. head. The weight of the type AS 30 is only 15 lb. and its frequency is 12,000 r.p.m.

RANALAH STEEL MOULDS



STRAIGHT KERB MOULD

Solidly constructed Standard Moulds of many types from stock or specially made to your drawings. Speedy and competitive. Kerb, Garden Edging, and Coping Moulds to B.S. 340-1950. We make a speciality of the prompt delivery of radius kerb moulds. Other moulds ex stock or in a few days. Send for illustrated catalogue of standard moulds. Accurate and very strongly made.

RANALAH

STEEL MOULDS LIMITED

43 DEVONSHIRE PLACE · BRIGHTON · SUSSEX · Tel: 22191/4.



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically Indefinite : all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

UNI-TUBE

PLIABLE STEEL TUBING

Ducts for stressed concrete . . . labour saving . . . easy to install . . . outer ribbing gives a perfect bond to the surrounding concrete . . . the inside of the tube is smooth to facilitate the passage of bars or cables and allows free flow of grout.

Supplied in $\frac{1}{8}$ " up to 6" i.d.

As approved and supplied for the Lee-McCall, Freyssinet and Gifford-Udall systems. Also suitable for other systems and designs.

FOR
STRESSED
CONCRETE

UNI-TUBES LTD


Enquiries to London Office:

9 South Molton Street, W.1 Telephone: Mayfair 7015


Works: Alpha Street, Slough.

Telephone: Slough 25476 8

Supplied to leading contractors throughout the world.



The news you've been waiting for...



Years of research and rigorous testing have resulted in a Diesel engine as robust and reliable as the Land-Rover itself. An alternative to the famous Petrol engine, this Rover-designed, Rover-built Diesel combines tremendous thrust and pulling power both on and off the road with all the economy of diesel operation. Petrol or Diesel, this is the ideal vehicle for fetching, carrying and towing around the farm or factory. Furthermore, when fitted with centre or rear power take-off, the Land-Rover provides mobile or stationary power capable of operating all kinds of machinery.

Regular Land-Rover, Petrol: £615; Diesel £715

Long Land-Rover, Petrol: £690; Diesel £790



Now a choice of
PETROL or DIESEL



THE ROVER CO. LTD., SOLIHULL, WARWICKSHIRE and DEVONSHIRE HOUSE, PICCADILLY, LONDON

CVS-186

CUT YOUR CONCRETE COSTS

with the

A.B. MOULD

MIXER-DRIVE SHOVEL

ALL BRITISH DESIGN AND MANUFACTURE
(Patent applied for)

At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button controlled shovel.

THE BUILT-IN JIB ELIMINATES
SITE INSTALLATION COSTS.



LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS
NO RUNNING COSTS
FITTED TO MOST MIXERS

Ask for a demonstration from :

A. B. MOULD & CONSTRUCTION CO., LTD.

VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY


Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

Underpinning by Pynford

- ★ **SITE INVESTIGATIONS** that are clear and to the point
- ★ **NEW FOUNDATIONS** designed and/or constructed to suit all site conditions
- ★ **UNDERPINNING** by the proved **Pynford method** for high-level beams, or below ground level
- ★ **JACKING** Re-levelling existing buildings and cheap provisions for new buildings
- ★ **EXCAVATING SHIELDS** supplied for digging to any depth through shifting ground such as sand mixed with water

Illustration shows a steel stool acting as shear reinforcement in a Pynford Underpinning Beam



Pynford Limited


Patentees

Foundation Engineers, Site Investigations,
Underpinning, Jacking

74 LANCASTER ROAD, STROUD GREEN
LONDON, N.4

Telephone: ARChway 6216/7

speed-up the contract with




supplied cut to required lengths or bent to schedule ready for fixing

This service has an excellent reputation in the reinforced concrete industry for accuracy in bar-bending to schedules, reliability, prompt delivery to the site, and economy. Quotations submitted at short notice for contracts of all sizes in any part of the country.

PASHLEY & TRICKETT, LTD.

Stoke St., Sheffield, 9. Tel: 41136-7



Trent Gravels

10,000 tons per week

Washed & Crushed 1½ in. to ¾ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Beeston 54255.

"CONCRETE SERIES" BOOKS ON CONCRETE


For a complete catalogue giving prices in sterling and dollars, send a postcard to:
CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1



Ten Mile Creek, Oregon, U.S.A.




Naragala Bridge, Ceylon



New Gandy Bridge, Florida, U.S.A.



Water Street Bridge, Auckland, N. Zealand



Mahi Bridge, Vasad, Nr. Baroda



Merdeka Bridge, Singapore



Langstone Bridge, Hampshire, England

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone : ROTHERHAM 2076 (P.B. Ex. 8 lines)

London Office : 8-10 GROSVENOR GARDENS, S.W.1.

Telephone : SLOane 0428

Birmingham Office : 83 KINETON GREEN ROAD, OLTON, SOLIHULL

TEL : ACOCKS GREEN 0229

Portsmouth Office : 23 & 25 SPUR ROAD, COSHAM.

TEL : COSHAM 78702



SEALING LEAKAGE BY CEMENTATION



The illustrations show drilling and pressure grouting being carried out to an old concrete dam at Cynwyd Reservoir, N. Wales, for the Edeyrnion R.D.C.

Extensive pressure grouting was necessary to increase the cement content of the concrete in the Dam and to fill fissures in the underlying rock.

Consulting Engineers: Richards & Dumbleton; Birmingham and Portmadoc.

WHITLEY MORAN AND COMPANY LIMITED

Specialists in the Repair of Engineering Structures
5 OLD HALL STREET, LIVERPOOL, 3
Tel: CENTRAL 7975/6 Grams: GUNITE, Liverpool, 3

Ensure
safety
with

DORMAN LONG Steel Trench Sheet

(Regd. Design No. 850,839)

The ideal for temporary lining,
easy to drive: can be used over and over again

PROMPT DELIVERY Prices and full particulars on application to


DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1




STONE COVERING PAINT

WHAT IT IS - AND HOW TO APPLY IT

THIS BOOK WILL TELL YOU



STONE COVERING—Fine Stipple



STONE COVERING—Coarse Stipple

You will find this booklet very useful. It describes the complete range of Stic B Products, their application and use by the Architect and Builder. Included also is a comprehensive report by the Building Research Station on the conditions under which our products were tested, and the impressive results that were achieved. Please write to our London office, when a copy will be sent you by return.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD, VAUXHALL, LONDON, S.W.8

Telephone: RELiance 5566

**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
BATHS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

GUNITE
CONSTRUCTION CO. LTD
WESTERN HOUSE, HITCHIN, HERTS.

Telegrams :
Gunite
Hitchin

Telephone :
Hitchin
4371



**DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.**

Quotations on Application.

Telephone: Paddington 2924 (3 lines).

**WASHED
BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete**
WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,
**IRONGATE WHARF,
PADDINGTON BASIN, W.**
MEMBERS OF B.S. & A.T.A.

**“THE CONCRETE YEAR BOOK”
1957 EDITION**

ORDER YOUR COPY NOW

1164 PAGES. PRICE 10s. By Post 11s. 6d. \$2.40 in North America.

CONCRETE PUBLICATIONS LTD., 14 Dartmouth Street, London, S.W.1.

JOHN HEATHCOAT'S WEAVING SHEDS

TIVERTON, DEVON

Prestressed concrete decreases costs in factory construction



Heathcoat's factory at Tiverton, Devon, has recently been extended using prestressed concrete valley beams and northlight roof trusses. The first section uses six beams of 56 ft. span. The second phase consists of 14 beams arranged in two 50 ft. spans. The third and last section uses 10 beams of 108 ft. span.

* Some further details of this project and others are published in brochure form. Write for your copy now.

Sponsor: JOHN HEATHCOAT
& CO. LTD.,
TIVERTON,
DEVON.

Architect: ALEC FRENCH,
F.R.I.B.A.,
BRISTOL.

Design by: STRESSED CON-
CRETE DESIGN
LTD., LONDON,
S.W.4.

Contractors: WM. COWLIN
& SON LTD.,
BRISTOL.



Ever since prestressed concrete construction was first used in this country, designers, architects and civil engineers have specified "Wire by Johnsons." The reason is quality, built up on early experimental work with those specialist designers who studied and worked on the Continental development of this new building technique.

Johnsons have a long record of "Firsts" including indented wire for greater bonding and coils of 8 ft. diameter, from which the wire pays out straight.

wire was essential —

Johnsons of course!

Richard Johnson & Nephew Ltd., Manchester, 11

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.

ALEX J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAIlsworth 1115/6



D.S. 14

accurate particle size analysis

Vibration alone or hand shaking is not sufficient for accurate particle size analysis of materials. Vibration alone is more inclined to aggregate the particles. The Inclyno Test Sieve Shaker ensures perfect segregation of the various particle sizes in the shortest possible time having a double movement of gyrating and jolting the test material.

The Inclyno Test Sieve Shaker is an essential unit for all laboratories and is standard equipment in many Government laboratories, nationalized industries and industry in general.


Operated by a fractional h.p. motor and supplied complete with automatic time switch covering test periods up to 60 minutes. Models available for all sizes of standard test sieves.

INCLYNO

TEST SIEVE SHAKER

Write or telephone Crawley 25166 for List IN 1607

THE PASCALL ENGINEERING CO. LTD.
GATWICK ROAD • CRAWLEY • SUSSEX




Look for the name **ALLAM**
and buy the best
VIBRATING EQUIPMENT
made today

**FLEXIBLE DRIVE
INTERNAL
VIBRATOR**



The most comprehensive range of Allam internal vibrators includes petrol, electric and pneumatic types with frequencies up to 11,500 r.p.m., and all offered with three sizes of interchangeable vibrating units to suit very harsh dry concrete mixes, various cross-sections, and spacing of reinforcement.

External vibrators are offered in five sizes to suit the size and shape of the member to be concreted. They are used as complementary to internal vibrators, or where the section and reinforcement exclude the entry of internal vibrators.



**TRILLOR
ELECTRIC
EXTERNAL
VIBRATOR**

Details of these and other items of contractors' plant sent on request.

E · P · ALLAM & CO. LTD.

LONDON : 45 Great Peter Street, S.W.1.

Telephone : Abbey 6353 (5 lines)

SCOTLAND : 39 Cavendish St., Glasgow, C.S. Tel. : South 0186. Works : Southend-on-Sea. Tel. : Eastwood 55243

CONCRETE PROOFING Co. LTD.

GUNITE SPECIALISTS

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.

96, Victoria Street, Westminster, S.W.1

Telephone :
VICTORIA 7877 and 6275



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

★ We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone : 3385-6

LONDON OFFICE : 17 QUEENSBERRY WAY, S.W.7. Telephone : KENSington 3583

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTUL"

Regd. Trade Mark

British Made

Extra-High Frequency




INTERNAL CONCRETE VIBRATORS

- The model illustrated here operates 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.
- Petrol or Electric Drive.
- Robustly built throughout and backed by genuine service.
- Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for : SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

High Strain patented Steel Wire for Prestressed Concrete

Manufactured by-




LEE

OF SHEFFIELD

TRUBRITE STEEL WORKS - MEADOW HALL - SHEFFIELD
Tel. : Sheffield 387272

London Office: Stafford House, 40/43 Norfolk St., Strand, W.C. 2. Tel.: Temple Bar 7187
& 7188. Birmingham Office: 191 Corporation St., Birmingham 4. Tel.: Central 6801 & 6802



Between dusk
and dawn

Concrete in **HOURS** *not* days

When it's a question of usable strength at real speed no other type of cement can approach CIMENT FONDU.

Many concreting jobs can be put into use even in a few hours ; 24 hours is the *maximum* waiting time.

CIMENT FONDU is not "quick-setting" and gives ample time for placing ; considerable strength develops after about 6 hours.

Please ask for leaflet "Between Dusk and Dawn"



The Cement for Industry

FOR SPEED : STRENGTH

RESISTANCE : REFRACTORINESS

Manufactured by

LAFARGE ALUMINOUS CEMENT COMPANY LIMITED

73, BROOK STREET, LONDON, W.1 Telephone : MAYfair 8546

A NEW

MATOBAR

REINFORCEMENT

by McCALLS

ROAD MESH

Write for a brochure to:-

McCALL & CO. (Sheffield) LTD
TEMPLEBOROUGH SHEFFIELD P.O. BOX 41

Tel. : Rotherham 2076 (P.B.Ex. 8 lines)

London Office : 8-10 Grosvenor Gardens, S.W.1. Tel. : SLOane 0428. - Also

Birmingham : 83 Kineton Green Rd., Olton, Solihull. Tel. : Acocks Green 0229

Portsmouth : 23 and 25 Spur Road, Cosham. - Tel. : Cosham 78702

GLASCRETE

at

St. Basil's Church BASILDON

Architects


Messrs. Burles & Newton

A.A.R.I.B.A., A.M.T.P.I.

The entire natural lighting to this church is provided by Glascrete windows of which this end feature is an interesting example. Concrete Tracery to the baptistery and doorways further illustrates the adaptability of Glascrete.

J. A. KING & CO LTD

181 QUEEN VICTORIA STREET
LONDON, E.C.4 CEN. 5866



*The watertight P.V.C. Expansion Joint
for all concrete structures subject to
water pressures.*

IN THE END THEY

WILL SEE

WHY YOU CHOSE




DURAJOINT

Durajoint has a specially designed ribbed section which ensures effective bonding with concrete, prevents movement of the strip, eliminates percolation of water and renders sealing compounds unnecessary — the central hollow tube accommodates lateral movement between adjacent sections of concrete. Durajoint is tough, non-ageing, resistant to water, acids and alkalis, weatherproof and unaffected by extremes of temperature. It can be easily handled and is available in rolls of various lengths, in widths of 2½", 3½", 6" and 9". Write for full technical details.

"Durajoint" is a registered trade name.

There is nothing to compare with DURAJOINT

An Arctic Grade is available to withstand temperatures from 100°C. to -60°C.



THE MICANITE & INSULATORS CO., LTD.,

EMPIRE WORKS, BLACKHORSE LANE, WALTHAMSTOW, LONDON, E.17.

Tel: Larkwood 5500. 'Grams: "Mycilite", Easphone, London.

WOODEN TROUBLE-FREE MOULDS

delivered
to the site
ready for use

The mould illustrated below was supplied by us to Concrete Development Co., Ltd., for producing 75-ft. precast reinforced concrete posts for Messrs. Holland & Hannen and Cubitts, Ltd.



SUB-LET YOUR MOULD CONTRACTS

and save time, labour, and money on your contracts.

moulds for all precast structural members and other concrete units

An exacting service for the supply of wooden moulds is now available to all Contractors engaged in producing on the site precast concrete for frame structures and other types of buildings. We are fully equipped to produce moulds to your design—however intricate—for all classes of precast concrete, which we guarantee to be accurate in every detail and strongly constructed to give the maximum number of castings. Economical prices and early delivery assured for contracts in any part of the country. We also specialise in the supply of ready-to-use timber shuttering to any design.


MAY & BUTCHER LTD

HEYBRIDGE BASIN, MALDON, ESSEX. TELEPHONE: MALDON 698

Specialists in



Reinforced



Concrete



STAVERTON BUILDERS LIMITED



Building and Civil Engineering Contractors
TOTNES DEVON

OFFICES AT : LONDON • CARDIFF • BRISTOL • PLYMOUTH


AND NOW MILLS SELF-LOCK PROP

SIMPLEST SAFEST LIGHTEST

**NO PINS, NO NUTS TO LOSE • NO THREADS
TO CLOG OR WEAKEN • NO CHAINS TO BREAK
• WEIGHS ONLY 24 lbs. (PLUS INNER TUBE)**

Operates from 5' 6" up to any height required using the base unit and standard scaffolding tube. Secured by inserting the inner tube into the outer, the inner tube being automatically clamped by a simple movement of the locking lever. The locking device cannot be released by accident.

The graph below, shows the results of exhaustive tests on the Mills Self-Lock Prop, using standard scaffolding tube. It clearly indicates that the Mills Self-Lock Prop, with tube at an overall height of 8 ft., has a Safe Loading of 4.1 tons. Even with a Loading of 8.1 tons the Mills Self-Lock Prop remained undamaged, although the tube buckled.



Apart from normal application as shown, the Mills Self-Lock Prop can be used at any angle—even upside down. The Mills Self-Lock Prop locking device allows fine adjustment to be made under load.

(Top curve) Ultimate Test curve for Self-Lock Prop with 5' 6" base tube and 8' long scaffold tube inner.
(Centre curve) Typical strut failure curve, 2" scaffold tube with base and head plates.
(Bottom curve) Safe Load curve for Mills Self-Lock Prop


MILLS SCAFFOLD CO. LTD. A subsidiary of Guest, Keen & Nettlefolds Ltd.

HEAD OFFICE: TRUSSELY WORKS, HAMMERSMITH GROVE, LONDON, W.6. TELEPHONE RIVERSIDE 5011 (10 lines)



WORLD
WIDE
PATENTS

FOR HANDLING CEMENT IN BULK...



Fully proved on hundreds of sites, the Portasilos is the most highly developed, fully portable equipment in the world for handling cement in bulk. The unique Pullway Mechanical Cement Man provides fully automatic weighing of the cement, without which the full saving of using cement in bulk cannot be achieved. The use of the Portasilos readily effects a saving of 18/- and over per ton of cement used.

One of four Portasilos in use on the construction of the New B.P. House which is to be leased to the British Petroleum Co. Ltd.

Arch. Messrs. Joseph F/FRIBA
10 Lowndes Square, London, SW1
Main Contractors, Myton Ltd.
Head Office, 169 Clough Road,
Hull. London Office,
10 Park Street, London, W1.

...there's nothing like the

PORTASILO
1955

PORTASILO LIMITED • BLUE BRIDGE LANE • YORK • Tel. 24872 (8 lines)

AND AT LONDON BIRMINGHAM MANCHESTER GLASGOW BELFAST DUBLIN

Covered by patents or patent applications in Great Britain and the Principal countries of the world

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LII, No. 7.

LONDON, JULY, 1957.

EDITORIAL NOTES

Technical Training in the U.S.S.R.

THE great advances in technology in the U.S.S.R. have led to deputations from other countries to study the training of technicians in that country. A recent deputation to visit the U.S.S.R. for this purpose comprised professors and lecturers of technical subjects at British universities and others concerned with technical training in this country, and a report on their investigation has now been published.* Major differences were found. For example, because of the scarcity of buildings, the courses are often worked two shifts a day, one from 8.30 a.m. to 2.15 p.m. and the other from 3 p.m. to 9 p.m. Evening classes are from 6 p.m. to 11 p.m. It is stated that the tests applied to students are less stringent than in Great Britain, and some of the Russian students who received diplomas would not have done so here. During his first two years at college a Russian student has some training in a workshop and time is given to foreign languages and general education, and during the last three years he spends about six months in industry. Only the fourth and fifth years are devoted to detailed study of a specialised branch of industry. At the Leningrad Polytechnic Institute only half of the full-time staff have higher degrees; personal ability is the chief consideration in the appointment of staff. Teaching appointments are reviewed every five years. Some lectures are given to three hundred students at a time in halls where visibility for seeing demonstrations is poor. The proportion of women students varies from one-fifth in heavy technology such as power engineering to four-fifths or more in the lighter branches such as metallography. Women students in all branches of engineering comprise about half the total number of students, compared with about 1 per cent. in Great Britain. In the U.S.S.R. the average age of entry to the higher technical institutes is seventeen, the length of the course is five years or longer, the working week is of six days, there are thirty or more weeks of instruction each year, and the total hours of instruction in the course are between 4500 and 5100. It is seen that the teachers and students have much less spare time in the Soviet Union than in Great Britain, where instruction is given for only twenty-five to thirty hours a week during twenty-four weeks a year. In Soviet Russia technical students are exempt from military service.

The delegation was naturally handicapped by the short duration of the visit

* "Engineering Education in the Soviet Union." Obtainable from the Institution of Civil Engineers, the Institution of Mechanical Engineers, and the Institution of Electrical Engineers.

(nine days) and the language difficulty. Some of the report deals with matters that the members saw, but much of it repeats what they were told; the report states, however, that there is no reason to doubt its accuracy. The principal purpose of the delegation was to see what could be learned of the Russian educational system that could be applied in this country. In this it was not successful, due to the differences in the standards that were acceptable in each country and the difficulty of relating Russian standards to British. On the basis of a standard that would satisfy the examiners for associate membership of one of the major British engineering institutions, the number of men who reached this stage in Great Britain in the year 1954-1955 is said to be about five thousand. This can be compared only with the number awarded a diploma by an engineering institute in the U.S.S.R., and these are said to total 65,000 a year. Thus on the basis of the populations of the two countries the proportion of the people trained in engineering is about four times as great in Russia as in Great Britain. Whether the young British engineering graduates are better than the Russian the delegation is not able to say, but the report expresses some doubt on this point when in a badly-written sentence it states that "we would not be complacent about our young engineers even if they were greater than the Russian figures on a population basis".

The report is interesting but inconclusive, and its effect is spoilt by an endeavour to use it as propaganda for higher salaries for university staffs. It is stated that teaching is the highest-paid profession in the U.S.S.R., and that whereas a director of a teaching establishment is paid 7000 roubles a month a "director of a large enterprise" is paid only up to 6500 roubles a month. It is not, however, pointed out that in the U.S.S.R. a director of a large enterprise is not, as in this country, responsible to the shareholders for increasing business and dividends. The Russian director is a manager of a State-owned enterprise who is not responsible for getting business; also, he is paid a bonus based on costs. It is also stated that in the U.S.S.R. the teaching staffs can increase their incomes by undertaking research work for the government, whereas in Great Britain "some Government departments" do not allow university staffs to receive payment for research work done for these departments. In Russia those engaged in education are said to have "perquisites" in that motor-cars, living accommodation, and holiday camps are made available to them, whereas in the United Kingdom there are no "perquisites" for such people. It might, however, be mentioned that in Great Britain university staffs can and do buy a car or a house when they wish to do so. Also they can and do arrange their holidays to their liking in this or another country, and may consider this to be better than staying at a State-owned camp. It may further be pointed out that fees for consulting work and research may be, and are, received by university staffs in the United Kingdom from commercial firms, and that members of university staffs often arrange their lectures in book form, or write books, and receive royalties on their sale. When we compare conditions in Great Britain with those in the U.S.S.R., with its working week of six days, eight weeks' annual leave (no bank holidays), and the appointments "reviewed" every five years, it seems that our university staffs have little reason to envy the Russian director of a teaching establishment for receiving about the same salary as a works manager and "perquisites" that few British directors of teaching would wish to replace freedom of choice.

Reinforced Concrete Structures in Berlin.

A FEATURE of the International Building Exhibition being held in Berlin from July 6 to September 29 this year is an exhibition of models, photographs, and drawings of many of the more outstanding structures built in Berlin in recent years or now in course of construction. Some of these are described and illustrated in the following.

The new Berlin Congress Hall (*Figs. 1 to 4*) is being built by the Benjamin Franklin Foundation to the design of the American architect Mr. Hugh A. Stubbins, with whom two German architects, Messrs. Werner Duettmann and Franz Mocken, are co-operating.

Due to the marshy nature of the site, the building is founded on 500 precast

piles 33 ft. long and with a bearing capacity of 50 tons each and 260 in-situ piles to carry 100 tons each. The building covers an area 330 ft. square. The main entrance leads into a two-story hall in the middle of the ground floor, around which are rooms and halls. The building also includes an exhibition hall of 10,500 sq. ft., a theatre with seating for 500, offices, a conference room to accommodate 200 people, a restaurant, and a post office, etc.

A platform will extend around the hall at first-floor level, supported on reinforced concrete columns. The main auditorium, with a floor area of about 12,500 sq. ft. and seating capacity for 1200 people, is supported on reinforced concrete columns.




Fig. 1.—Congress Hall, Berlin.




Fig. 2.—Congress Hall, Berlin.




Fig. 3.—Longitudinal Section, Congress Hall, Berlin.




Fig. 4.—Cross Section, Congress Hall, Berlin.

The shape of the roof is intended to give the impression that it is floating over the building. Its shape is that of a saddle. It rests at the east and west on reinforced concrete beams about 10 ft. deep and 22 ft. wide. These are joined to two curved hollow beams, each 400 ft. long, between which the roof declines. The greatest height of the curved beams is 60 ft. The roof cantilevers 25 ft. beyond the beams, and is designed as a shell.

Fig. 5 shows an exhibition hall just completed at Berlin to the design of Mr. Bruno Grimmek. The hall has a floor area of more than 80,000 sq. ft. The structure is a composite steel and reinforced concrete construction. A mezzanine floor is suspended from the roof by high-tensile steel bars, so that the ground floor is free of columns. The frames, which span 165 ft., are of pre-stressed concrete, spaced 40 ft. apart,




Fig. 5.—Exhibition Hall, Berlin.




Fig. 6.—Residential Flats, Berlin.




Fig. 7.—Residential Flats, Berlin : Front Elevation.




Fig. 8.—Residential Flats, Berlin : Rear Elevation.




Fig. 9.—Roman Catholic Church, Berlin.




Fig. 10.—Residential Flats, Berlin.

and the precast reinforced concrete purlins are 6 ft. 6 in. apart. The roof slab is of aerated concrete 3 in. thick. The total height of the frames is 61 ft.

The residential flats shown in *Fig. 6* are seventeen stories high and cover an area of nearly 5000 sq. ft. The architects are Professor Klaus Mueller-Rehm and Mr. Gerhard Siegmann. The walls are of reinforced concrete cast in place, and the outer walls are faced with precast concrete slabs of story height including a layer of insulating material.

The residential flats shown in *Figs. 7* and *8* (architects Messrs. Fritz Jaenicke and Sten Samuelson of Malmö, Sweden) will be 281 ft. long by 33 ft. wide by 100 ft. high and will contain 68 flats. The building will be a reinforced concrete framed structure with walls of lightweight precast slabs.

The church shown in *Fig. 9* is being built in the Berlin Hansa district to the

design of Professor Willy Kreuer. The plan of the nave is similar to a parabola. One side of the curve, nearest to a railway, is an unbroken wall so that services will not be disturbed by railway traffic. The other sides have large areas of glass. The church will be of reinforced concrete. The plain wall is to be painted on the inside, with the colour becoming lighter towards the altar. The spaces between the columns of the other walls will be filled with precast concrete and glass.

Residential flats designed by Professor Walter Gropius and Professor Wils Ebert and to be built in Berlin are shown in *Fig. 10*. The structure will be about 82 ft. high, 33 ft. wide, and 275 ft. long. The building is to be in framed reinforced concrete. The outer walls will be in white concrete, and the fronts of the balconies will be covered with white enamelled steel. The window frames are to be of aluminium.

The Volume of Construction.

ACCORDING to the Ministry of Works, the total value of building and civil engineering work done during the first quarter of the year 1957 was £525,000,000, compared with £474,000,000 in the first quarter of the previous year. The number of men employed in these industries was 1,060,000 in the first quarter of 1957 compared with 1,073,000 in the first quarter of 1956.

The index number of the cost of new construction increased from 134 in the first quarter of 1956 to 139 in the first quarter of 1957. The value of work done by direct labour by Government departments, local authorities and nationalised industries was £83,000,000 in the first quarter of 1956 and £87,000,000 in the first quarter of 1957.

Estimating the Size of Rectangular Sections.

By F. H. TURNER, B.Sc., A.M.I.C.E., A.M.I.Struct.E., D.I.C.

FOR preliminary designs and estimates a rapid but approximate method of determining the size of sections is frequently required. It is assumed that the span, total load, maximum bending moment, and maximum shearing force have already been evaluated, that the section is to have not less than the "economical" depth, and that no reinforcement to resist shearing forces is desired. The following notation is used: d , effective depth; b , breadth; l , span; w , uniform load per foot; W , total load; S , maximum shearing force; M , maximum bending

moment; A_s , area of tensile reinforcement required; $k = \frac{M}{Wl}$; $k_1 = \frac{S}{W}$; $k_2 = \frac{d}{l}$;

$$k_3 = \frac{b}{l}.$$

Since d^2 must be equal to or greater than $\frac{M}{Qb}$, and $\frac{S}{a_1 b d} = 100$,

$$k_2^2 l^2 > \frac{k W l}{200 k_3 l} \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and

$$\frac{k_1 W}{a_1 k_2 k_3 l^2} = 100 \quad . \quad . \quad . \quad . \quad . \quad (2)$$

From equation (2), since $a_1 = 0.85$, $k_2 k_3 = \frac{k_1 W}{100 a_1 l^2} = \frac{k_1 W}{85 l^2}$.


Substituting in equation (1), $\left(\frac{k_1 W}{85 l^2}\right) k_2 l^2 > \frac{k W}{200}$. Therefore $k_2 > \frac{0.425 k}{k_1}$.

METHOD.—Evaluate $k_2 = 0.425 \frac{k}{k_1}$, and $k_2 k_3 = \frac{k_1 W}{85 l^2}$. Select the line representing $k_2 k_3$ on Graph I. Any pair of co-ordinates to this line indicates a cross section with sufficient resistance to the shearing force. Select a section such that k_2 is greater than $\frac{0.425 k}{k_1}$. This indicates a section that will also resist the bending stresses.

The area of reinforcement required can be calculated from $A_s = \frac{M}{15,500 d}$. The graph is plotted with equal vertical and horizontal scales so that the ratio between the depth and breadth of the section is not distorted. This gives an additional visual indication of the most suitable section. Larger cross-sectional areas than those indicated may be used, making the shearing stress correspondingly less than the maximum permissible stress.

EXAMPLE I.—A beam spans 15 ft. ($l = 180$ in.), the total load is 30,000 lb., the maximum bending moment is 1,000,000 in.-lb., and the maximum shearing force is 20,000 lb.

$$k_1 = \frac{2}{3} = 0.67; k = \frac{1,000,000}{30,000 \times 180} = 0.185. \quad \frac{0.425 k}{k_1} = \frac{0.425 \times 0.185}{0.67} = 0.1175.$$

Graph No. 1.—Curves Corresponding to Various Values of $k_r k_s$.

$$k_2 k_3 = \frac{k_1 W}{85 l^2} = \frac{0.67 \times 30,000}{85 \times 180^2} = 0.00727.$$

Mark the minimum depth (0.1175) on the graph. The corresponding breadth is 0.063, which gives a reasonable section. Adopting these sizes,

$$d = 0.1175 \times 180 = 21.1 \text{ in. and } b = 0.063 \times 180 = 11.4 \text{ in.}$$

Make the beam 2 ft. by 1 ft., and $A_s = \frac{1,000,000}{15,500 \times 21.1} = 3.06 \text{ sq. in.}$

EXAMPLE II.—A cantilevered beam projects 6 ft. ($l = 72 \text{ in.}$), the load is 35,000 lb., and the maximum bending moment is 2,100,000 in.-lb.

$$k_1 = 1. \quad k = \frac{2,100,000}{35,000 \times 72} = 0.833. \quad 0.425 \frac{k}{k_1} = 0.425 \times 0.833 = 0.355.$$

$$k_2 k_3 = \frac{k_1 W}{85 l^2} = \frac{35,000}{85 \times 72^2} = 0.0795.$$









From the graph, $k_2 = 0.4$ and $k_3 = 0.2$ give a reasonable section. Therefore $d = 0.4 \times 72 = 28.8 \text{ in.}$, and $b = 0.2 \times 72 = 14.4 \text{ in.}$ Make the beam 2 ft. 6 in.

by 1 ft. 3 in., and $A_s = \frac{2,100,000}{15,500 \times 28.8} = 4.7 \text{ sq. in.}$

The various constants are shown in Table I for the common conditions of loading. If several beams are to be estimated a table can be made under the headings k_1 , k , $\frac{0.425k}{k_1}$, $\frac{k_1}{85 l^2}$, $d = k_2 l$, $b = k_3 l$, and $A_s = \frac{M}{15,500 d}$.

The method can be adapted to obtain approximate dimensions for tee-beams by evaluating $k_2 k_3$, where $k_3 = \frac{\text{breadth of rib}}{\text{span}}$, and determining the minimum value of k_2 corresponding with the known ratio $k_3 = \frac{\text{breadth of flange}}{\text{span}}$.

TABLE I.

LOADING	k_1	k	$0.425 \frac{k}{k_1}$	$\frac{k_1}{85 l^2}$
	0.5	0.25	0.213	0.00588
	0.5	0.125	0.106	0.00588
	0.5	0.16	0.142	0.00588
	0.5	0.10	0.085	0.00588
	0.5	0.125	0.106	0.00588
	0.5	0.083	0.071	0.00588
	1.0	1.0	0.425	0.01175
	1.0	0.5	0.213	0.01175

EXAMPLE III.—A continuous tee-beam spans 25 ft. between supports. The bending moment at a support is 2,500,000 in.-lb. and at midspan 2,000,000 in.-lb. The total load is 100,000 lb. and the maximum shearing force 60,000 lb. The breadth of the flange is 60 in.

Rectangular section at the supports:

$$k_1 = 0.6, k = \frac{2,600,000}{100,000 \times 300} = 0.083; 0.425 \frac{k}{k_1} = \frac{0.425 \times 0.083}{0.6} = 0.0059,$$

$$\frac{k_1 W}{85l^2} = \frac{0.6 \times 100,000}{85 \times 300^2} = 0.0078.$$

From the graph it is seen that a very wide section is required to resist bending. Adopting a section such that $k = 0.15$ and $k_3 = 0.065$, $d = 0.15 \times 300 = 45$ in. and $b = 0.065 \times 300 = 19.5$ in. Use a section 48 in. by 21 in.

$$\text{Tee section at midspan: } d_{min.} = \sqrt{\frac{M}{Qb}} = \sqrt{\frac{2,000,000}{200 \times 60}} = 18.1 \text{ in.}$$

Since the shearing stress at midspan is small no further investigation is required and the depth at midspan may be reduced to, say, 21 in.


In the design of continuous beams it is usual to provide reinforcement to resist the shearing forces. This can be taken into account by assuming a constant nominal shearing stress and decreasing the calculated values of $k_2 k_3$ in the ratio

100

"nominal" shearing stress

Adjusting the Level of Foundations.

A METHOD of adjusting the level of the foundations of a building which may be subjected to variable settlement has been devised by the French engineer M. Albert Caquot and is being used in Le Havre in the "Porte Océan", a building of fourteen stories, where a variable settlement of $2\frac{1}{2}$ in. is expected. The accompanying cross section through a column and foundation illustrates the method. The lower part of the column is reduced in size so that it may pass through a ring-beam anchored to the foundation. This ring-beam contains a bed of sand laid on top of the foundation, on which the precast base of the column is placed. Extending from the top of the precast base are reinforcement bars placed so as to lap with the longitudinal reinforcement of the remainder of the column to be cast in place. A tube passes through the ring-beam to the bed of sand and is sealed by a removable cap at its outer end. When it is necessary to alter the level of the base



of the column the cap is removed and an auger is inserted into the sand so that by rotating the auger some of the sand is removed and the base of the column slides down within the ring-beam. Another tube passes through the precast base to the sand so that it is possible to inject cement-grout under pressure to raise a column or to stabilize the sand at any desired level. The foregoing is abstracted from a recent number of the Belgian journal "La Technique des Travaux".

Design of Reinforced and Prestressed Bridges.

By DR. RICCARDO MORANDI.

THE following is an abstract of a lecture entitled "Modern Conceptions in the Planning of Bridges in Reinforced Concrete and in Prestressed Concrete", read by Dr. Riccardo Morandi, the well-known Italian engineer, at a meeting in London organised by the Joint Committee on Structural Concrete under the auspices of the Cement and Concrete Association.

flexible at the crown and the springings, in which the deck would be supported on the arch by vertical slabs disposed so as not to offer any resistance to the deformation of the arch due either to its own weight or to live loads. The arch (Figs. 1 and 2) is a cellular structure of a total depth of 3 ft. 6 in. at the crown and 11 ft. 6 in. at the springings. The bottom




Fig. 1.—San Nicola Bridge, Florence.




Fig. 2.—San Nicola Bridge, Florence : Half-longitudinal Section.

The works described were all designed by the lecturer.

Arch Bridges.

For the reconstruction of the San Nicola bridge over the river Arno in Florence, destroyed in the war, a single arch with a span of 290 ft. and a rise of 26 ft. was used. For this bridge it seemed opportune to abandon completely the concept of an arch with stiffening slabs and to use a curved beam equally

flexible at the crown and the springings, in which the deck would be supported on the arch by vertical slabs disposed so as not to offer any resistance to the deformation of the arch due either to its own weight or to live loads. The arch (Figs. 1 and 2) is a cellular structure of a total depth of 3 ft. 6 in. at the crown and 11 ft. 6 in. at the springings. The bottom

slab is 1 ft. thick throughout most of its length, and near the springing there are vertical slabs at about 10 ft. centres. The top slab has a constant thickness of 1 ft. The cellular structure projects beyond the springings for about 112 ft. It is supported on inclined hollow piles and filled with sand and gravel; this contains the resultant of the forces at the level of the foundation within an angle of 32 deg. to the vertical. Excluding the foundations,




Fig. 3.—Paguita Bridge, Caracas.

3.28 cu. ft. of concrete and 24.8 lb. of mild steel were used per square foot of deck. The behaviour of the bridge when the centering was removed, during tests, and in use showed that the modulus of elasticity is 4.97×10^6 lb. per square inch.

The Paguita bridge (Fig. 3) in Caracas, Venezuela, is a shallow arch spanning 295 ft. and rising barely 23 ft. The thickness of the arch, especially at the abutments, had to be kept as small as possible, and the bridge is at an acute angle of skew; also the horizontal thrust of the arch had to be as little as possible because of the nature of the soil. Prestressing was of great help in solving the problems, and it was possible to experiment with the concept of self-regulation of the funicular polygon by applying diagonal forces along the arch. An arch with such a small rise produces a thrust of considerable magnitude on the foundations, and because the abutments rested on soils of completely different physical characteristics the piled foundations had to be different. The structures above the piles were prestressed in order to resist, with as little deformation as possible, the high bending and shearing stresses caused by the non-convergence of the resultants of the forces transmitted by the arch.

The arch, which is at an acute skew, is a curved cellular structure composed

of upper and lower slabs and transverse slabs between the arch and the deck. At the crown the structure is about 3 ft. deep and at the springings about 8 ft. The design of such a thin vault with a small rise was much influenced by the difference in rigidity at the crown and the springings. It was believed that the skew would cause the vault to act differently from the theoretical behaviour. For example, the difference between the moment of inertia of a section normal to the lower slab and that of a section normal to the upper slab is much greater at the springings than at the crown. For this reason the arch was divided into a number of independent beams tied only by transverse slabs whose function is to cause all the girders to deform identically at given distances from each springing. The calculations for the vault made allowance for the oblique forces transmitted by the deck supports, which produce forces in the arch counteracting its thrust, so changing the value of the bending moments and producing economical design.

Near the abutments the resultant of the forces was kept within the required limits by prestressing. The calculations had to allow for the effect of the additional forces due to prestressing, since the prestressing force does not act at the centres of gravity of the sections, and for a further reduc-



Fig. 4.—Lupara Bridge, Genoa.

tion of thrust resulting from the axial contraction produced by the pre-tensioned cables. As a result the quantities of concrete and steel per square foot of deck were reduced from 3.3 cu. ft. and 26.5 lb. per square foot for the San Niccola bridge to 2.64 cu. ft. and 18.2 lb. per square foot for the Caracas bridge in spite of the reduction in the rise of the arch.

The advantages achieved in the last example apply to any arch. An arch is economical if the bending moments are similar throughout its span; a great difference in thickness at the crown and at the springings should always be avoided. An arch has been designed with the thickness at the crown greater than that at the abutments. This is not economical,

designed by Dr. Morandi) and the Caifa bridge, of the Maillard type, are similar and both have a span of 390 ft. In the Lupara bridge, 3.15 cu. ft. of concrete and 22.5 lb. of steel were used per square foot of deck; in the Caifa bridge, 4.35 cu. ft. of concrete and 28.5 lb. of steel were used.

In Italy, tubular steel centering of the Innocenti type (*Fig. 5*) is frequently used for the construction of bridges with long spans because it is light and can be erected and dismantled rapidly. It is sufficiently rigid to reduce considerably the effects of distortion owing to the deformation of the centering. For the Lupara bridge 200 tons of steel centering were used. It is desirable that the



Fig. 5.—Steel Centering (Innocenti type).

and the modern tendency is to make the thickness at the springings slightly greater than at the crown. In all arch bridges the roadway consists of a system of beams of multiple spans more or less horizontal, and prestressing may be used to lighten the structure. In the construction of very large bridges, the elastic behaviour of the piers must be considered. The most economical results can be obtained by using isolated supports which taper and have their greatest moment of inertia at the road and their least at the arch, thus causing little distortion of the arch.

A comparison between the amounts of concrete and reinforcement required for this type of arch and those required for an arch designed by the elastic method, originally devised by Maillard, is of interest. The Lupara bridge (*Fig. 4*,

centering should be removed gradually so as to develop as slowly as possible the stresses in the arch due to its own weight.

At present, the Cruciani type of timber shuttering (*Fig. 6*) is being much used, even for arches spanning more than 300 ft.

Bridges with Horizontal Beams.

For bridges with straight beams of reinforced concrete the internal stresses due to the live load are almost always small compared with those due to the dead load. Attempts have been made to reduce the dead load, and it is now possible to build beams with high-strength concrete and ordinary reinforcement for spans of some 160 ft. with the use of about 1.65 cu. ft. of concrete per square foot of deck. For a bridge in reinforced concrete the ratio of dead load to live



Fig. 6.—Wooden Centering (Cruciani type).

load per unit of surface is about one; for a prestressed concrete structure it is about 0.6 to 0.7. This ratio may be reduced by further developments, but eventually the effects of excessive deformation will have to be considered.

Although it is generally believed that prestressed concrete is not as suitable as reinforced concrete for simply-supported beams of small span, bridges of simply-supported beams have been built in which prestressing has been used to obtain lightness and economy for spans of 70 ft., using a series of prestressed concrete beams on existing supports. Each beam comprises five webs of ovoidal section tied by the upper slabs and by transverse members. The profile of the sections is made economically possible by casting

the various elements in quantity, using steel shuttering and the vacuum process. The design made the maximum use of the material employed, although the maximum stresses were similar to those adopted for other prestressed structures. For each square foot of deck, 0.96 cu. ft. of concrete, 3.4 lb. of high tensile steel, and 3.7 lb. of mild steel were used. Because of their light weight the various precast members were easily handled on the site (Fig. 7).

A bridge with a simply supported span of 125 ft. was constructed using a prestressed concrete beam, shaped so as to be of uniform strength throughout its length, composed of three boxes tied together by the upper slab and by eleven transverse members. The depth of the




Fig. 7.—Transporting a Beam.

structure is slightly over 6 ft. at mid-span and under 4 ft. at the supports. The high-tensile steel prestressing wires of $\frac{1}{4}$ -in. diameter were tensioned to 140,000 lb. per square inch. The abutments are of reinforced concrete. The slenderness ratio of the beams (depth to length) is 0.0475. For each square foot

region (Fig. 8). The bridge consists of three parallel frames (Fig. 9), slightly arched, restrained at the foundations, and with tapering piers (Fig. 10). The three frames are tied together by two end-blocks at the piers, by the upper slab, and by the bottom slab near the piers. There are also thirteen transverse slabs which




Fig. 8.—Garigliano Bridge.




Fig. 9.—Garigliano Bridge: Transverse Section.

of deck 1.3 cu. ft. of concrete, 5.6 lb. of high-tensile steel, and 5.7 lb. of mild steel were used. The use of simply-supported beams for spans longer than 125 ft. is not economical.

Hollow "Box" Girders.

Good foundation conditions allowed the use of a statically-indeterminate structure for the Garigliano bridge, in the Giunture

ensure that all the frames act together under moving loads. The frames, which have a span of 200 ft. and a height of 31 ft., are entirely prestressed.

The San Niccola bridge at Benevento is a double cantilever frame with hinges at the base of the piers (Figs. 11 and 12). The overall length is 390 ft. with a central span of 260 ft. The supports each consists of eight columns 1 ft. 4 in. thick

and tapering from 13 ft. to 4 ft. 6 in. wide, which are hinged to a cellular base designed to transmit a pressure of $3\frac{1}{4}$ tons per square foot to the foundation. The deck is supported by four hollow beams, with walls 5 in. thick and varying in depth from 8 ft. 10 in. to 11 ft. 8 in., joined by a top slab 5 in. thick, and over part of the span by a bottom slab. There are also twenty transverse members of varying height and thickness. Concrete with a minimum strength of 6400 lb. per square inch was used. The prestressing steel was high-tensile steel $\frac{1}{8}$ in. diameter (minimum ultimate strength of 256,000 lb. per square inch, and an elastic limit of 214,000 lb. per square inch). The secondary reinforcement consists of round mild-steel bars.

It would be dangerous to prestress a beam of this length after it had been fixed at its supports, since the contraction would cause deformation at the joint between the supports and the beams, and reduce the restraint of the beams. Two temporary rocker bearings were inserted between the supports and the beam so that the beam could contract freely under the prestressing force. With the beam simply supported on the columns, the centering was removed in such a way that, under the permanent loads, the bending moments at mid-span were reduced due to the action of the cantilevers. The rocker bearings were then fixed so that the structure acted as a statically-indeterminate frame under live loads.

By means of tension rods, bending moments can be produced at the ends of a beam in a sense opposite to those due to the external loads. Although the principle is simple, it is difficult to apply to bridges because the tension rods undergo variations in length as a result of the normal deformations of the beams to which they are attached and may become fatigued due to variation in stress. Care must be taken, therefore, in deciding the allowable range of stress. The bridge over the Cerami river in Sicily (Fig. 13) is designed so that the loads are transmitted to each support by two connecting members, one in tension and the other in compression. The structure has an overall length of 250 ft.

The bridge over the river Oreto near Palermo (Figs. 14 and 15) comprises a continuous prestressed concrete beam



Fig. 10.—Gariigiano Bridge: Detail of Support.

resting on oblique elastic members forming two trestle supports, which are hinged upon two bases supported on piles. The bridge has a central span of 182 ft., two side spans each 68 ft. long, and two end cantilevers each 36 ft. long. The width of the roadway is 49 ft. and each pavement is 8 ft. wide.

Proposed Span of 1300 ft.

The design proposed for a bridge, 5.6 miles long, across the Maracaibo lagoon



Fig. 11.—San Nicola Bridge, Benevento.




Fig. 12.—San Nicola Bridge, Benevento.




Fig. 13.—Bridge over the Cerami, Sicily.



Fig. 14.—Bridge over the Oreto, Palermo.



Fig. 15.—Bridge over the Oreto, Palermo.

in Venezuela is shown in *Figs. 16 and 17*. The entire structure would be in prestressed concrete with ten spans of 490 ft. and one span of 1300 ft. All the spans provide a minimum vertical clearance of 150 ft. At the ends of the central section, comprising the central span of 1300 ft. and the two spans of 490 ft. adjoining it, there would be two X-shaped supports. The external arm supports the adjacent span, and the other arm contains the tension ties for both spans and acts as a support. The two extremities of the section, affected by the passage of loads upon the three spans of the section, would be stressed either in compression or tension. The continuous beams would be supported on piers on either side of the central span, and by elastic supports sloping down from two towers 210 ft. high. At the centre a simply-supported beam would be suspended between the ends of the continuous beams and would move independently with variations of temperature.

After the construction of the continuous beam, and while it was supported

on centering, two temporary hinges would be formed, as shown in *Fig. 18*, at the central support. Then the tension members of high-tensile steel wires would be tensioned so that the two parts of the beam were raised clear of the centering. In this way the tension members would support the weight of the beam without elongation (except that caused by thermal variation) and there would be no distortion of the central support by the beam because of the temporary hinges. The horizontal component of the oblique force in the cables which pass over the towers would produce a compressive force along the plane of the centre of gravity of the beam which, together with the force produced by the prestressing cables in the same beam, would provide the precompression required. Under these conditions the inclined tension members would be stressed so that the structure would be stable under its own weight. The simply-supported central beam would then be placed in position joining the two balanced systems. After some days, when equilibrium had been reached, the inclined




Fig. 16.—Design for Maracaibo Bridge, Venezuela : Central Part.




Fig. 17.—Design for Maracaibo Bridge.




Fig. 18.—Design for Maracaibo Bridge: Central Part.

tension members would be encased in concrete, but the wires could be free to move in their ducts. After this, the cables would be further prestressed in order to compress the concrete sheath, and the cables grouted. Finally the temporary hinges at the central supports would be fixed.

A New Periodical.

IN the year 1954 the organisations representing the cement and concrete industries in Denmark, Sweden, Norway, Finland, and Iceland combined to form the Nordisk Betonforbund (North European Concrete Association), and the new association has now produced the "Nordisk Betong" ("Northern Concrete"). The editorial board comprises representatives from Denmark, Finland, Norway, and Sweden. The editor is Mr. Sven G. Bergstrom, of Sweden, and the journal is published at Drottning Kristinas 26, Stockholm. The journal is printed in the Swedish language, with summaries in English, and the annual subscription rate is 20 Swedish kroner.

The first number contains a description by Caspar Trumpy of the Puddefjord bridge, Norway, with a central arch span of 150 metres in reinforced concrete; details of the standard specifications for

concrete and reinforced concrete in Denmark, Finland, Norway, and Sweden, by Viljo Kuuskoski; a paper on torsion in slabs, by Jørgen Nielsen; a paper on the creep of concrete subjected to loads for long periods, by Lars Östlund; and a review of recent research in the countries concerned.

Gold Medal Awarded to M. Eugène Freyssinet.

THE gold medal of the Institution of Structural Engineers is this year awarded to Monsieur Eugène Freyssinet, the eminent French engineer, who has taken a leading part in the development of prestressed concrete. This is the first time that the Institution has awarded its gold medal to a non-member. It is hoped that Monsieur Freyssinet will be present to receive the award.

Floors without Projecting Beams.

Mr. E. SHEPLEY, B.Sc., M.I.C.E., of the Trussed Concrete Steel Co., Ltd., writes as follows:


Your May number has an Editorial Note which shows how an inexact terminology has arisen in prestressed concrete. In the same issue there is a description of an office building in London, and on the cover the floors are described as "flat-plate".

We must be careful with the terminology of concrete plate construction, because these floors appear to be con-

ventionally supported—for the very purpose of avoiding beam action.

It is considered inherent in plate design that the loads find their way directly to the main supports by natural paths normal to the contours of deflection, whereby shear, torsion, bending and direct actions are compounded into a minimum entropy state which permits the engineer to design with the utmost economy of both steel and concrete.

Several examples of folded-plate construction have been illustrated in your



ventional hollow clay-tile slabs carried by beams of the same total depth, resulting in a flat ceiling. I would restrict the term "plate" to solid construction akin to steel-plate work, where a plate may be flat, folded, dished, curved, domed, corrugated, etc. It is admitted that in the building described the introduction of parallel rows of "pots" forms a ribbed plate, but the loads from the ribs are transferred to the shallow beams and columns in a perfectly standard fashion, and the floor can hardly be described as a flat plate. A plate could, of course, be ribbed to improve its buckling resistance, but in this case the ribs would be made relatively small and would not be inde-

pendent, and, of course, all shell construction would come under my definition as curved-plate work. True flat-plate designs for multiple story flats and office buildings have been constructed by the Trussed Concrete Steel Co., Ltd., by their Truscon Plate System, and I believe one or two buildings have been constructed with plates of variable thickness which have been referred to as "taper plates".

The illustration is of an industrial office building, designed for an imposed load of 50 lb. per square foot, in course of construction by the Truscon Plate System. The columns are 10 in. by 10 in. in cross section and the floors 5½ in. thick.

Prestressed Concrete Bridge for Heavy Loads.

By E. A. L. KEITH, B.Sc.(Eng.), A.C.G.I., A.M.I.C.E.

THE preliminary civil engineering work for the new power station now being built at High Marnham, Notts, included the construction of a bridge (Fig. 1) to carry a road over new railway sidings to the power station. As this road is the most suitable approach to the power station for transporting the stators and transformers, allowance had to be made for very heavy loads.

A transformer and its transporter, which has 3-axle bogies, together weigh about 240 tons, thus exceeding the 45-unit highway-bridge loading. For a stator and its transporter, which together weigh 210 tons, the load is only slightly less as the transporter has 2-axle bogies. Since

including a composite girder and reinforced concrete slab, but the most economical and speediest form of construction was found to be prestressed precast beams with post-tensioned steel with concrete infilling and slab as shown in Fig. 2.

The deck is composed of twenty-seven beams, nearly I-shape (Fig. 2), placed side by side with the $\frac{1}{4}$ -in. nibs touching. The spaces between the bottom flanges were filled with cement mortar, the nibs acting as shuttering, and then concrete was placed to fill the spaces between beams and form a slab 3 in. thick above the top flanges. Two sheets of saturated bituminous felt were placed on this layer of



Fig. 1.

these abnormally heavy loads will probably occur infrequently, the bridge was designed for the 45-unit Ministry of Transport highway-bridge loading so that the pre-compression in the bottom flanges of the beams would be zero under this loading, and an allowance was made for temporary overloading by abnormal loads. This design ensures compression in the bottom flanges of the beams under normal Ministry of Transport loading, which is considered desirable for bridges over railways. The bridge will also be adequate to meet future requirements if, as seems probable, this road is given a higher classification.

Although the existing road was re-aligned and re-levelled, the revised clearance for over-bridges of 15 ft. 6 in. required by British Railways seriously limited the depth of construction of the deck. Several schemes were considered,

concrete, and the top layer of concrete was formed to the correct camber, with longitudinal falls towards the road gulleys at the ends of the approaches. The beams (Fig. 7) were made in a factory, and were prestressed by the Gifford-Udall system; Lee-McCall high-tensile bars were used for the transverse prestressing.

The span is 34 ft. $4\frac{1}{2}$ in. and the width between the parapet walls 45 ft., the roadway occupying the central 22 ft. The bridge has an angle of skew of about 20 deg., so that, contrary to the usual practice, transverse stressing could only be arranged satisfactorily parallel to the abutments. Correct alignment of the beams was important, and it was therefore decided to tension only two wires of each cable at a time to avoid any lateral deformation. In addition, the $\frac{1}{4}$ -in. nibs at the sides of the beams were omitted and the beams made $\frac{1}{4}$ in. narrower to provide




Fig. 3.—Sectional Elevation at Centre-line of Beam.

greater tolerance if lateral deformation occurred. The beams were true after prestressing, and there was no difficulty in seating and aligning the transverse ducts.

Ducts for services were formed on both sides of the bridge by using shallower beams adjacent to the parapet beams. These ducts were lined with asphalt $\frac{1}{8}$ in. thick, and covered with precast slabs over which the tarmacadam of the pavement will be carried after the services have been laid in the ducts. The cross sections of the beams are similar. Of the 27 beams used, 23 are identical; the beams under the ducts have a narrower top flange, and the parapet beams are wider and have a rounded arris at the outer bottom edge to facilitate the escape of smoke (Fig. 8). Thus only three types of beams were used and the same moulds were used for all of them. The use of similar beams under the roadway and the pavements makes it

possible to widen the roadway, if required, without difficulty.

The bearing-plates are of special interest. The phosphor-bronze plates are recessed in the main steel body of the top plates to prevent them working loose. A transverse boss in the top plate and a corresponding slot in the bearing surface of the bottom plate effectively anchor each beam laterally.

Details of a fixed bearing are shown in Fig. 5. The sliding bearings are very similar in construction but provide tolerance to permit longitudinal movement and deflection. Further details of the seatings at the abutments are shown in Fig. 6. An angle bolted to the soffits of alternate beams near the ends encloses the bearings completely and thus prevents fouling by birds. Smoke-baffles are suspended from the underside of the deck above the centre-line of each track. The whole of the underside of the bridge, including the



Fig. 4—Beams in Position.




Fig. 5.—Details of Fixed Bearings.




Fig. 6.—Details of Seating at Abutment.



Fig. 7.—Beams Ready for Erection.



Fig. 8.—A Parapet Beam.

baffle-plates, the protection plates, and all exposed surfaces of bearings, nuts, bolts, etc., were painted with two coats of heavy-bodied bituminous paint.

A cornice was cast in place to cover the anchor-plates and anchor-nuts of the transverse stressing bars; a precast cornice above this feature was continued at the top of the wing walls. In the abutment and wing walls, trapezoidal horizontal grooves were arranged at regular vertical intervals to hide the construction joints between successive lifts, and the surface was bush-hammered to within an inch above and below these grooves. At a late stage in the work a realignment of the sidings resulted in the tracks being curved under the bridge, and it was necessary to corbel the eastern half

of the north abutment in order to provide the specified clearance. This corbel is visible only from the cutting for the station sidings and has not detracted from the appearance of the bridge.

The cost of the works, including abutments, wing walls, road surfacing, parapets, etc., was about £4 12s. 6d. per square foot. The clients were the Central Electricity Authority, and the bridge and the roadworks associated with it have been taken over by the Nottinghamshire County Council. The contractors were Messrs. M. J. Gleeson (Contractors), Ltd., and the beams were made by the Kingsbury Concrete Co., Ltd., at their works about ten miles distant from the site. The consulting engineers were Messrs. Freeman, Fox & Partners.

Design of Silos.

THE design of deep beams for walls of silos, using methods devised by Dischinger, is explained in a recently-published German book.* From the diagrams and tables, the distribution of stress σ_x , the total tension T , the lever arm d , and the distance d_0 from T to the lower edge of the beam (Fig. 1) can be easily obtained for a continuous girder, with an infinite number of spans, for the usual types of loading. The values of T , d , and d_0 for single-span beams can be calculated, using the special case in which the width of the support is equal to half the span.

Navier's straight-line law appears to apply to deep girders, provided that the depth of the beam does not exceed two-fifths of the span for single-span girders, or four-fifths of the span for continuous girders. Above these values the distribution of stress deviates considerably from the straight-line law.

In silo walls, beam action is shown to occur mainly near the lower edge. In the case of a continuous girder the effective depth can be assumed to be about equal to the span.

The total tension was found by integrating the tensile stresses, and it was established that when $\frac{H}{L}$ is less than two-fifths the lever arm of the internal forces is proportional to the depth of the beam, but when $\frac{H}{L}$ is greater than or




Fig. 1.




Fig. 2.

equal to 0.45 the lever arm is a function of the span.

It is considered wrong to stiffen the walls of silos by providing additional edge beams; the reinforcement in such beams is stated to be ineffective because of the stiffness of the wall; the arrangements shown in Fig. 2 are recommended.

An important conclusion is that the top reinforcement over the supports of deep beams should not be at the upper edge of the beam, but in a position determined from the diagrams, as shown in Fig. 3; in this illustration a represents nominal reinforcement, at b are indicated suspended bars if the load is applied below (as in hoppers), C indicates small bars to resist shrinkage and secondary stresses, and D is the main reinforcement.

* "Hilfsstafeln zur Berechnung Wandartiger Stahlbetonträger." By Otto F. Theimer. (Berlin: Wilhelm Ernst & Sohn. 1956. Price 7.20 D.M.)




Fig. 3.

The Terminology of Prestressed Concrete.

MR. JAMES N. LOWE, M.A., A.M.I.C.E.,
of the Pre-Stressed Concrete Co., Ltd.,
London, writes as follows.

SIR,—In your Editorial Notes for May 1957 you do a service in drawing attention to the confusion of thought in the terminology used in prestressed concrete and, I suspect, use some deliberate exaggeration to impel your readers into replying. I feel sure you will succeed in your aim.

First of all, may we define the process we wish to name as "the application of a system of forces to a structure or structural member before it is called upon to withstand working loads". The reasons for applying the process are numerous, and vary from fundamental structural reasons to useful tricks. In applying the process to a medium, we choose the system of forces to restrict the stresses at any time to those which the medium will accept. In applying the process to concrete, therefore, we limit the total compressive stress to that acceptable and permit very little or probably no total tension.

Therefore, before applying working loads we apply forces, and these forces cause stresses which are both compressive and tensile. Hence a logical name for the process is "pre" (that is before applying working loads) plus "stressed" (that is the result, both tensile and compressive, of applying forces). Hence the word prestressed. Indeed the incorporation of the term "stressed" is a healthy reminder that the application of this process causes all forms of stress, including bending, shearing, and torsional, positive and negative, and it invites the engineer to ensure that at all stages these kinds of stress are within the capacity of the particular medium. I submit therefore that "prestressed" is short and pithy and is understood, and is therefore acceptable.

The next stage is to find names for the methods of applying these forces, bearing in mind that over the years we shall see great changes. How often nowadays do we refer to the Hennebique System?—we talk about reinforced concrete. We may well see a similar change in prestressed concrete, but the principle of prestressing will be applied in many ways and

for many new purposes, so we must not presume too much in giving names now or we may cause confusion later.

The particular terms we want at the moment are for use where the system of forces applied is the result of the position, the shape, and the load of high-tensile steel wires or bars. We want to differentiate between the two basic methods of doing this. The two methods vary in the time when concrete is cast, in the way in which the steel passes its forces to the concrete, and in the consequent techniques of design.

In one method the tension of the steel is maintained by anchoring its ends with devices cast in the concrete; its position is maintained likewise; the shape is maintained by ducts cast in the concrete. In this case the steel is tensioned after the concrete has matured.

In the other method the tension in the steel is maintained by bond with the concrete; its position is maintained likewise—so far it does not seem to be practical to impose a shape. The steel is tensioned before the concrete is cast, the tension being temporarily resisted by abutments, and this force is transferred from the abutments to the concrete, to which it is bonded, after the concrete has matured.

Thus the two methods are seen to have many complex differences: the time of casting the concrete, the time of tensioning the steel, the shaping of the steel, the method of transferring the tension in the steel to the concrete, and more are involved. The words to describe these two methods should be simple and short, should indicate complexity, and should be chosen for use by the expert.

The immediate differentiation between the methods can be achieved by using "pre" and "post" to indicate whether the steel is tensioned before or after the concrete has been cast and matured. The word "tensioned" is added, giving "pre-tensioned" and "post-tensioned". These portmanteau adjectives should, of course, be applied only to the steel. For example, we may speak of prestressed concrete and say that the prestressing is achieved by a method using post-tensioned steel or by a method using pre-tensioned steel. These are the three portmanteau words, the one indicating

simplicity of thought and the other two indicating complexity of method. It is necessary to have a word rather than a long phrase, not only for simplifying writing but also for simplifying specifying, billing, and both private and public speaking.

I believe too that the term "at transfer" is both simple and accurate. It refers to the transfer of anchorage from abutments to concrete bond, and calls upon the engineer to exercise all that care which he would exercise when transferring a load from one support to another.

I think there are two more important pieces of confusion that you refer to. It is dangerous, illogical, and useless to refer to tensioned steel as reinforcement. The prestressing steel is an external system of forces which is active. Reinforcement is a passive potential supply of tension in a medium unsuited to resist such tension. Your use of tensioned steel and untensioned steel for prestressed concrete and reinforcement for reinforced concrete are sound.

You are also right to advocate referring to abutments for pre-tensioned steel, though I prefer "anchorages" to "fixings" for post-tensioned steel because fixings occur in other parts of engineering and building.

I find it very difficult to provide for myself a universal terminology for the parts of the anchorages and the equipment for the various systems, but strongly believe that the years will see a simplification—perhaps an elimination—of method, as

we saw in reinforced concrete, and with some cowardice I leave further suggestions until that time.

[We are pleased to see that our correspondent agrees with all our suggestions except the use of the word precompressed instead of prestressed. As he suggests, precompressed is probably more accurate, because the purpose of prestressing is to "permit very little or probably no total tension", but the word prestressed is now too well entrenched for a change to be made.

We do not agree that technical terms "should be chosen for use by the expert" only. They should also clearly express their meaning if we are to meet the common complaint that scientists and technologists use so much jargon that they cannot be understood by others, and which may mean the opposite of their everyday meanings. We see no reason why such terms should indicate complexity, or why it should be necessary for a designer to use a term which will indicate to him that he is dealing with a complex problem—if he does not know that he should not be allowed to design in prestressed concrete. Nor do we believe that the mere use of the meaningless "at transfer" reminds the engineer "to exercise all that care which he would exercise when transferring a load from one support to another". If we say "when the prestress is applied" we describe exactly what we mean, and equally well remind the engineer that a force is transferred from the steel to the concrete.—EDITOR.]

Reinforced Concrete for Government Buildings.

REPLYING to a question in the House of Commons recently, the Minister of Works stated that it was estimated that the amount of steel used in building last year was $1\frac{1}{2}$ million tons. Reinforced concrete was now generally adopted for Government buildings unless there was a good reason to the contrary. During the year ended June, 1956, some 160 framed buildings of all types were designed by the Ministry, and of these 110 were in reinforced concrete. In the case of the second half of the new Government

buildings in Whitehall Gardens, London, reinforced concrete was being used instead of structural steel and as a result there was a saving of £130,000.

Lectures on Road Materials.

LECTURE courses dealing with the properties of road materials and the application of the results of research will be held at the Road Research Laboratory, Harmondsworth, during the autumn and winter of 1957-58. Full details can be obtained from the Director, Road Research Laboratory, Harmondsworth, West Drayton, Middlesex.

"OSAL" QUALITY PRODUCTS

**INDISPENSABLE
for CEMENT work**



A liquid for integral Hardening, Waterproofing and resistance to Acids and Oils, incorporated throughout the whole thickness of Concrete, Granolithic and Cement Renderings, etc., by absolute positive equal distribution.



A liquid for the surface Hardening of existing Concrete, Granolithic and Stone. Gives protection against Dusting, Acid and Oils. Increases resistance to wear and atmospheric disintegration.



A colourless liquid applied to the surface of Brick, Stone, Concrete, Renderings, etc., which penetrates into the surface and acts as a water repellent.



A liquid mixed with the gauging water for plasticising Bricklaying Mortar, and cement and sand renderings. Increases workability improves adhesion, reduces efflorescence and risk of cracking or crazing—without the use of lime.




See Our Exhibit

A. A. BYRD AND CO., LIMITED (Dept. 5)

210, Terminal House, Grosvenor Gardens, London, S.W.1

'Phone : SLOane 5236.

'Grams : Byrdicom, Wespnone, London.



the right cure for bacon
is oak chippings...

the right cure for concrete is
"Ritecure"

*Illustrating the one-man
spraying operation.*



As tested and proved under all climatic conditions

One application of RITECURE MEMBRANE CURING material provides an impervious film controlling evaporation throughout the curing period of 28 days. The colourless liquid (applied while concrete is wet) has a temporary colour indicator added to aid application and inspection but this disappears after a few hours. One gallon covers approximately 30 square yards of concrete. Complete in itself, RITECURE requires no wetting down or covering and provides increased compressive strength and resistance to surface wear.



FREE ADVISORY SERVICE

With 20 years' practical experience our technical department can offer constructive assistance on specific concrete problems including the preparation of complete specifications.

Write for full technical information **STUART B. DICKENS LIMITED**

36 Victoria Street, London, S.W.1. Telephone: Abbey 4930 & 6157. Works: Manor Way, Boreham Wood, Herts. Telephone: Elstree 2211

Aggregate from Pulverised-fuel Ash.

THE first plant in this country for the production of concrete aggregate from pulverised-fuel ash is now in operation, by the Cementation Co., Ltd., at the Battersea (London) power station of the Central Electricity Authority, under licence from Sinterlite, Ltd., and Dr. F. P. Somogyi, the inventor of the process. The cost of the main plant (Fig. 1) was £260,000.

The amount of this ash that has to be disposed of from power stations in Great Britain is nearly 4,000,000 tons a year,

The kiln measures about 40 ft. high by 10 ft. diameter and is of welded steel plate lined with refractory bricks. The temperature, which attains a maximum of about 1400 deg. C., depends upon the draught in the kiln, and is regulated by instruments linked with thermocouples inside the kiln. Each kiln has an annual capacity of about 50,000 tons of aggregate.

As there is enough carbon in the ash for combustion, no fuel is needed other than that required to kindle the fire at the start. In the burning process the carbon




Fig. 1.—Plant for producing Aggregate from Pulverised-fuel Ash.

and the cost of its disposal is about £1,000,000 a year.

The ash from the electrostatic precipitators is first delivered into bunkers from which it is delivered into a shallow circular pelletiser, revolving at an angle, where it is sprayed with water. In the revolving pelletiser, gravity and centrifugal force cause the damp ash to form into small balls, the size of which is regulated by the speed of revolution and the angle of tilt of the pelletiser. The pellets spill over the rim of the pelletiser into a conveyor which takes them to the kiln.

and any sulphur and other volatile compounds are driven off, rendering the final product inert. The process is continuous, the pellets slowly descending from the top of the kiln until they reach a revolving grate at the base through which the sintered pellets emerge to be screened, graded into sizes, and stored in hoppers.

The aggregate, which is known as Terlite, is made in three sizes, namely from $\frac{3}{8}$ in. to $\frac{1}{2}$ in. weighing 48 lb. per cubic foot, $\frac{1}{2}$ in. to $\frac{3}{4}$ in. weighing 50 lb. per cubic foot, and $\frac{3}{4}$ in. to dust weighing 52 lb. per cubic foot. Concrete made in

the proportions of 1 part cement to 8 parts aggregate without fine material weighs 68 lb. per cubic foot and has a compressive strength of 600 lb. per cubic foot. A mixture of 1 part cement to 2 parts fine aggregate and 3 parts of the larger aggregate weighs 92 lb. per cubic foot and has a compressive strength of 3000 lb. per square inch. The shrinkage on drying and moisture movement are each about 0.025 per cent., and this type of concrete has good properties of insulation and resistance to fire. It is nailable, and provides a key for plaster.

The most suitable water-cement ratio (including any water in the aggregate) is about 1.1 to 1.2. For example, similar

mixtures had a compressive strength of 1750 lb. per square inch with a water-cement ratio of 0.9, 2400 lb. with a water-cement ratio of 1.0, 2800 lb. with a water-cement ratio of 1.15, and 2400 lb. with a water-cement ratio of 1.3.

Tests have shown that concrete with 400 lb. of cement per cubic yard has a compressive strength of about 1200 lb. per square inch at 28 days; with 600 lb. of cement the strength is about 2800 lb.; with 800 lb. of cement, about 3750 lb.; with 1000 lb. of cement, about 4250 lb.

[Further notes on this type of aggregate were given in this journal for December 1956.]

Single-story Industrial Buildings.

A BROCHURE entitled "Single-story Industrial Buildings", issued by the Cement and Concrete Association, describes forty-five such structures, including structures with shell and north-light "shell" roofs and pitched and Mansard roofs of prestressed and reinforced concrete, both precast and cast in place.


The most common type of building comprises gable frames of precast reinforced concrete, but a warehouse at Hayes, Middlesex, has reinforced concrete frames spanning 89 ft. that were cast in place at 19 ft. 2 in. centres. The rafters are 4 ft. 3 in. deep at the column, tapering to a hinge at the crown.

A factory at Lowestoft (*Fig. 1*) has a north-light shell roof with a span of 86 ft. The valley-beams are supported on columns at 26 ft. 6 in. centres, and the valley-beams and upper edges of the shells are prestressed (the architects are Messrs. Buckingham & Berry, the engineers Twistell Reinforcement, Ltd., and the contractors Messrs. R. G. Carter, Ltd.). On the other hand, a factory in Yorkshire is covered by a shell roof spanning 88 ft. with reinforced concrete valley-beams at 42 ft. centres. The brochure can be had free from the Cement and Concrete Association at 52 Grosvenor Gardens, London, S.W.1.



Fig. 1.

a special service
for producers
of stressed
concrete



We illustrate here one
of a batch of Stelmo Stressing-
Bed ends (with an effective stressing-
width of 6ft. 6 in.) recently supplied
by us for a contract overseas.



STRESSING-BED ENDS

designed to meet your conditions and
guaranteed to be accurate in all details

In collaboration with leading stressed concrete specialists, the Stelmo Research Organisation now designs stressing-bed ends—easily adaptable for all requirements—which have proved to be of inestimable value for this class of work. This experience, which is world-wide, is available to all contractors and precast concrete makers who desire to add efficiency, with economy, to the production of stressed concrete. If you are considering the manufacture of prestressed units, CONSULT US NOW.



*the most comprehensive
mould service in the world*

STELMO LTD., 275 SHAKESPEARE ROAD, LONDON, S. E. 24

Telephone : Brixton 4201

It's the knowledge
of when and what
to add...



"Sternson"
products
ensure
improved
concreting

STERNSON No. 300

Waterproofing for concrete, mortar

STERNSON No. 310

Accelerator, Hardener, Waterproof

STERNSON No. 340

Accelerator, Hardener, Waterproof

STERNSON No. 355

Quick-set Liquid

STERNSON No. 600

Metallic Jointing Material

STERNSON No. 610

Metallic Bonding Material

STERNSON No. 620

Metallic Hardening Material

Specified by leading consultants, STERNSON PRODUCTS
are approved and used by Government Departments,
County and Borough Engineers, Civil Engineers
throughout the world. Unaffected by extreme climatic
conditions, the correct STERNSON formula
gives improved results with no increased labour cost.
Suitable for all forms of concrete construction.

STUART B. DICKENS LTD.

36 Victoria Street, London, S.W.1.

Telephone: Abbey 4930 & 6157.

Works: Manor Way, Boreham Wood, Herts.

Telephone: Elstree 2211.

★ **ADVISORY SERVICE**

With 20 years practical
experience our technical
department can offer construc-
tive assistance on specific
concrete problems including
the preparation of complete
specifications.

Consolidation by Vibration.

A JOINT committee was appointed by the Institutions of Civil and Structural Engineers in the year 1935 to consider the compaction of concrete by vibration. Interim reports were published in the Journal of the Institution of Civil Engineers for March 1937 and April 1938, and a report* recently published is more of the nature of a manual on vibrated concrete for the use of engineers and contractors.

After summarising the objects and uses of vibration, the committee considers how the efficiency of the process is affected by the characteristics of the materials, the proportions, and the shape and grading of the aggregates. It is recommended that coarse aggregates be ordered in different sizes so that they may be stock-piled and used to maintain constancy of grading, which is particularly important in leaner mixtures. Stock-piles should be arranged to avoid segregation of the coarse aggregate and to ensure uniform water content in both coarse and fine material. Batching by weight, compensation for variations in the water content of aggregates, apparatus for measuring workability, and the use of the compacting-factor apparatus are recommended.

Nearly half of the report deals with the selection of aggregates and mixtures made with continuously-graded aggregates and gap-graded aggregates. For continuously-graded aggregates the recommended method is that given in "Design of Concrete Mixes" (Road Note No. 4 of the Road Research Laboratory), modified slightly to suit vibrated concrete. The principal modification is the omission of the finest grading zone, leaving only three grading curves with two zones between them. These curves are otherwise the same as those in Road Note No. 4, but in Fig. 6 of the report, which gives gradings for 1½-in. aggregates, one gap-grading is added. The other tables are similar to those in Road Note No. 4 except that grading No. 4 is omitted from the relevant tables.

The steps in obtaining a suitable mixture with continuously-graded aggregate are as follows. (1) Knowing the minimum

strength required and the efficiency of the works control to be used, determine, with the help of Table 1 and Fig. 4, the average strength required and the corresponding water-cement ratio. (2) Use Table 2 to determine the degree of workability ("very low", "low", "medium" or "high"). (3) Use Table 3 or 4 to determine the aggregate-cement ratio and the most suitable grading. (4) From the sieve analyses of the proposed aggregates calculate proportions of the fine and coarse material that will produce a combined aggregate with a grading as close as possible to the selected curve. (5) Since the water-cement ratio and the aggregate-cement ratio have been obtained, all the proportions can now be decided. (6) A trial mixture on the site may show a need for small modifications in the calculated proportions, for example a small increase in the amount of mortar. Fully-worked examples are given to illustrate this procedure.

In the case of gap-gradings a theoretical method is recommended based on filling the voids in the coarse aggregate with mortar made with fine aggregates small enough to enter the voids in the compacted coarse aggregate; the result of the calculation must be checked by trial mixtures. Other recent work, however, suggests that this rather elaborate calculation might be avoided by determining the most suitable continuous grading and deriving the gap-grading from this; trial mixtures, which must be made in any case, indicate any modifications necessary.

Mixtures richer than 1:4 by weight are dealt with separately. The increase of strength with cement content for such concretes of constant workability is very much less than in the case of leaner concretes. Diagrams show the variations of crushing strength with the compaction factor for proportions of 1:2½ and 1:3½ with ¾-in. aggregate, and the variations of strength with water-cement ratio for 1:3 mixtures with ¾-in. and ¾-in. aggregates. The necessity for making trial mixtures with the selected proportions is emphasised.

There are paragraphs on shuttering and on mixers, the latter stating a need for a new type of mixer specially designed for

* "The Vibration of Concrete." Published by the Institutions of Civil and Structural Engineers. 57 pages. Price to members 3s. 6d.; to non-members, 8s.

stiff lean mixtures. Most of the remainder of the report is a discussion of immersion, clamp-on, table, and other vibrators, their methods of drive, characteristics, suitabilities and general use, and methods of placing concrete by vibration. Special attention is recommended in the use of surface vibrators on roads and runways so as to ensure a surface with good riding properties. Suggestions are made for further research. A very useful section gives recommendations for clauses of a specification for vibrated concrete. These would be additional to

the normal clauses, and are intended to ensure the adequate control of the materials and their proportions, the adequacy of samples, the tightness and freedom from distortion of shuttering, the choice of vibrators, the control of vibrators, and the control of the strength of the concrete.

The report is a compact handbook on vibrated concrete, concise enough for quick reference and yet full enough for ordinary use, and will be useful to site engineers and inspectors as well as to designers of concrete works.—H. N. W.

Change of Title.

THE title of Twisteel Reinforcement, Ltd., has been changed to G.K.N. Reinforcements, Ltd., in order to indicate its connection with the Guest, Keen & Nettlefolds group of companies and because the former title does not describe the work and products of the company, which now supplies all types of reinforcement. When the company was formed in 1924 it undertook the supply on a limited scale of square twisted bars and woven fabric. Its products now include Wireweld fabric, Tentor bars and fabric, prestressing wire, and round mild steel bars, and it also undertakes the design of concrete structures.

New Immersion Vibrators.

NEW immersion vibrators, known as "200 Cycle" machines, are now available from Messrs. E. P. Allam & Co., Ltd. The motor is within the vibrator, so dispensing with flexible leads. The electricity may be generated 100 yd. from the position where the vibrators are used. All the motors operate at low voltage, 200 cycles, three phase, and are made to withstand high temperatures. The standard sizes are 2 in. diameter by 17½ in. long, 2½ in. diameter by 18½ in. long, 3½ in. diameter by 18 in. long, and 1½ in. diameter by 35 in. long.

Anglian Building Products, Ltd.

Messrs. Boulton & Paul, Ltd., and Anglian Building Products, Ltd., announce that an agreement has been concluded by which Messrs. Boulton & Paul, Ltd., will take a financial interest in Anglian Building Products, Ltd., and its associated companies, Norwich Ready Mixed Concrete, Ltd., and Atlas Sand & Gravel Co., Ltd.

A Manual of Prestressed Concrete.

A BROCHURE on the use of post-tensioned steel bars in prestressed concrete has been issued by McCall Macalloy, Ltd., of Templeborough, Sheffield. The contents deal with design, detailing, tensioning the steel, and the application of this type of prestressed concrete to beams, frames, bridges, piles, caissons, tanks, and the strengthening of beams. A number of tables give some useful data, and in an appendix are described methods of making high-strength concrete. Copies of the brochure are obtainable free on application.

COMPLETE PLANTS DESIGNED • INSTALLED AND COMMISSIONED

SPECIALISTS IN

Reinforced Concrete • Structural
Steelwork • Mechanical Handling
Special-Purpose Plant
Products Design • Tooling

BRITISH-GECO ENG. CO. LTD.

ADELAIDE HOUSE, LONDON BRIDGE, E.C.4

Telephone : Mansion House, 8277

FOR SALE.

FOR SALE. Steel guttering, ironwork, and sheet metalwork. E. STEPHENS & SON LTD., Bath Street, London, E.C.1. Clerkenwell 1731.

FOR HIRE.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELL-MAN'S, 21 Hobart House, Grosvenor Place, London, S.W.1.

FOR HIRE. Travelling tower crane for immediate hire, Model G.12, complete with tracks and turntables. Keen rates. PLANT DIVISION, C.I. LTD., Staffa Road, Leyton, E.10. Telephone: Leyton 3678.

STAHLTON



Stahlton flooring being laid in the new factory for A.C. Delco, Division of General Motors Limited, at Kirkby, Liverpool. The architects for the project are Sir Alfred Shennan and Partners, and the main contractors Messrs. Lloyd and Cross Limited.

Stahlton floors and roofs were introduced into this country by the Costain organization in 1952.

Their many advantages found immediate acceptance. The clay or concrete blocks are light and easy to handle, simple to lay and require no specialised techniques. They are now being used on an increasing number of contracts—from hospitals in the Highlands to office blocks in London.

For fully illustrated particulars please contact—

COSTAIN

CONCRETE CO. LTD

LONDON & SOUTHERN COUNTIES.

Duncan House, Dolphin Square, London, S.W.1. Telephone: Victoria 3172/4

SCOTLAND & NORTHERN COUNTIES.

Coltness Factory, Newmains, Lanarkshire. Telephone: Motherwell 2331

WALES & WEST COUNTRY.

Cowbridge Road, Bridgend, Glam. Telephone: Bridgend 961

LANCS., YORKS. & MIDLANDS.

R. Costain & Sons (Liverpool) Ltd., Barlows Lane, Liverpool, 9. Telephone: Aintree 4141/5

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 4d. a word : minimum, 7s. 6d. Situations Vacant, 5d. a word : minimum, 10s. Other miscellaneous advertisements, 5d. a word : 10s. minimum. Displayed advertisements, 3s. per column inch. Box number 1s. extra.

Advertisements for the August number must reach this office by July 13th.

SITUATIONS VACANT.

SITUATIONS VACANT. Consulting structural engineers in new modern offices conveniently situated in Central Liverpool have vacancies for reinforced concrete and structural steel designer-draftsmen, in the salary range of £700-£1100 per annum. Special opportunities exist for those interested in nuclear energy projects, and appointments in this field carry additional increments in salary. Positions offered are permanent with excellent prospects. Staff bonus and superannuation schemes are in operation. Apply in confidence, giving age and full details of experience, to Box 4321, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. R. L. BOURQUI & PARTNERS, Thermix House, Kingston-on-Thames, require draftsmen immediately for reinforced concrete work. Only first-class draughtsmen with good printing and linework considered. Knowledge of design an advantage, but ability to detail from calculations essential. Should be able to construct general arrangement drawings from sketches of industrial structures, framed buildings, etc. Above-average salaries offered to competent and conscientious men. Full holidays this year. Telephone for appointment to Elmbridge 0439 (office hours) or Elmbridge 2654 (evenings).

SITUATION VACANT. Civil engineering draughtsman required for work in London office of large civil engineering contractors. Work of varied nature, with scope for initiative and advancement. Commencing salary £600-£800 depending on experience. Five-days week and luncheon vouchers. Pension scheme operates. Box 4228, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Assistant designer-draughtsman with up to 3 years' experience and/or technical training required for varied and interesting work on reinforced concrete and/or steel frame structures for industrial, commercial, medical, and residential buildings. Five-days' week. Lunch vouchers. Apply, with details of experience, and salary required, to JOHN F. FARGUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1.

SITUATIONS VACANT. Reinforced concrete detailers (senior) with considerable experience of industrial structures sought by TILMAN & CO. LTD., Romney House, Tufton Street, London, S.W.1, Civil Engineers and Contractors. Excellent prospects offered to capable men in enterprising and steadily expanding firm. Starting salaries around £900 per annum. Holiday arrangements respected. Write, or telephone Abbey 1551, for an appointment.

LONDON COUNTY COUNCIL

ARCHITECT'S DEPARTMENT

Vacancies for Engineering Assistants (up to £817) and Engineer Grade III (up to £1036) in the Structural Engineering Division.

The Division's work covers a programme of total value £12 millions this year, including multi-story flats, schools, office, warehouse and other buildings.

Particulars and application forms from the ARCHITECT (AR/EK/SE/3), The County Hall, London, S.E.1. (15.)

SITUATION VACANT. Reinforced concrete designer for work in Victoria Street, London. Five-days' week, non-contributory pension scheme after three years' service, and progressive position. Five years' or more experience with reinforced concrete specialists preferred. Write, giving full particulars, to THE SPENCER WIRE CO. (DEVELOPMENTS) LTD., 53 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete design engineers with considerable experience of industrial structures sought by TILMAN & CO. LTD., Romney House, Tufton Street, London, S.W.1, Civil Engineers and Contractors. Excellent prospects offered to capable men in enterprising and steadily expanding firm. Holiday arrangements respected. Write, stating experience, and salary required.

F. SHEPHERD & SON LTD.

Building & Civil Engineering Contractors

CONTRACTS MANAGER

required for

CONCRETE DEPARTMENT

Applications are invited from experienced men preferably under 38 years of age for a newly-established position as Contracts Manager for our Concrete Department operating from York. The company is substantial and well established and carries out a wide variety of building and civil engineering work mostly in Yorkshire and the North Eastern Counties.

The Concrete Department, already soundly established and continuing to grow, is a self-contained department within the main structure of the company, having its own design, estimating and production staff with specialist services available from the central organisation.

This new appointment involve responsibility for the supervision and management of all structural concrete work carried out on site by the Concrete Department both in the capacity of main and sub-contractors.

Applicants, preferably qualified as A.M.I.C.E., and/or A.M.I.Struct.E., must have enthusiasm, drive, substantial production experience, a keen interest in concrete technology and be capable of effectively taking charge of all aspects of structural concrete work on a group of contracts.

The position is permanent and offers attractive staff conditions including progressive salary, annual bonus, a non-contributory pension scheme and the provision of a car. The successful applicant will be required to reside in York but lodging away will not be necessary. Assistance will be given in securing a house if required.

Written applications, which will be treated in strict confidence, should state age, full details of experience, some indication of commencing salary required, and should be addressed for the personal attention of:

Mr. D. W. Shepherd,

Director

F. SHEPHERD & SON LTD.,

Building & Civil Engineering Contractors,

Blue Bridge Lane,
York.

SITUATIONS VACANT. Reinforced concrete designer-detailers required. Familiar with L.C.C. By-Laws, and with experience of frame structures. Five-days' week, luncheon vouchers, and pension scheme. Holiday arrangements will be unaffected. Write for interview to E. J. Cook & Co. (ENGINEERS), LTD., 54 South Side, London, S.W.4.

SITUATIONS VACANT. Consulting engineers require reinforced concrete designer-detailers for varied and interesting structures. Work will include some site supervision. High salaries will be paid to experienced men. Five-days' week, good conditions. Applications in strict confidence, stating full details of experience, and salary required, to ALAN MARSHALL & PARTNERS, 73-74 High Holborn, London, W.C.1.

SITUATIONS VACANT. Consulting engineers require reinforced concrete designer-detailers for varied and interesting structures. Work will include site supervision. High salaries will be paid to experienced men. Five-days' week, good conditions. Applications in strict confidence, stating full details of experience, and salary required, to ALAN MARSHALL & PARTNERS, 8 Cherry Street, Birmingham, 2.

SITUATION VACANT. Senior reinforced concrete designer required, preferably with specialist experience in the design of all types of reinforced concrete structures. A good salary will be paid in accordance with experience. A bonus scheme and non-contributory pension scheme are in operation. A five-days' week. Offices are adjacent to Victoria Station. Apply THE INDENTED BAR & CONCRETE ENGINEERING CO. LTD., Reinforced Concrete Engineers, 171 Victoria Street, London, S.W.1. Telephone: Victoria 1642.

SITUATIONS VACANT. One senior and two junior or intermediate draughtsmen required in civil engineering department of small consultant engaged on colliery work. Experience should be largely in reinforced concrete, but a knowledge of building construction, drainage, steelwork, etc., would be an advantage. Keenness and adaptability more use than vast knowledge. Good salary. A. BICKERDYKE & CO., 4-6 Hammersmith Grove, London, W.6. Telephone: RIVERSIDE 7452.

SITUATION VACANT. Prestressed concrete designer required for permanent and progressive position with opportunity for site experience. Five-days' week, luncheon vouchers and pension scheme. Holiday arrangements honoured. E. J. COOK & CO. (ENGINEERS) LTD., 54 South Side, Clapham Common, London, S.W.4.

SITUATION VACANT. Technical director required to be in charge of building materials' testing and research laboratories. The position offers good salary, participation in pension scheme, and housing accommodation. Please send applications, outlining previous experience, salary required, etc., which will be treated in confidence, to Box 4444, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

LONDON COUNTY COUNCIL

ARCHITECT'S DEPARTMENT

Vacancies for **ENGINEERING ASSISTANTS**, salary (up to £817) according to qualifications and experience.

Further particulars and application form obtainable from the Architect (AR/EK/DS/3), County Hall, London, S.E.1. (707.)

MIDDLESEX COUNTY COUNCIL

JUNIOR STRUCTURAL ENGINEERING ASSISTANT, APT.L (£543 ss. to £625 ss. plus £65 Westminster Weighting plus London Weighting of £30 per annum at 26 years and over, £20 at 21-25 years). To assist in detailing of frame structures in reinforced concrete and structural steelwork and preparation of steel schedules. Unestablished in first instance, subject to prescribed conditions. 5 days' 38 hours' week. Application forms (stamped and addressed foolscap envelope) from COUNTY ARCHITECT, 1 Queen Anne's Gate Buildings, Dartmouth Street, London, S.W.1, returnable by 20th July (Quote V.346 C.C.E.). Canvassing disqualified.

THE EXPANDED METAL COMPANY LTD.

Reinforced concrete designers and detailers required for permanent positions in London, West Hartlepool, Birmingham, and Manchester. Five-days' week. Staff pension scheme, etc. Apply in writing, giving brief details of experience, and salary required, to the Chief Engineer, THE EXPANDED METAL CO. LTD., 16 Caxton Street, London, S.W.1.

LONDON COUNTY COUNCIL

ARCHITECT'S DEPARTMENT

Vacancies for **STRUCTURAL ENGINEERS AND BUILDING SURVEYORS** for the District Surveyors' service. Starting salaries up to £817. Good prospects of career in interesting district work mainly outside. Particulars and application form, from the Architect, AR/EK/25/57, County Hall, London, S.E.1. (897.)

SITUATION VACANT. Udalls of Southampton require a civil engineer with good experience of prestressed structural and bridge design. Engineering degree essential; experience of applied research a recommendation. Salary £850 to £1000 per annum according to experience. Superannuation scheme available. Write to UDALLS, West Quay Road, Southampton, before July 31st.

SITUATION VACANT. Udalls of Southampton require a civil engineering draughtsman-detailer with at least six years' experience, preferably in prestressed or reinforced concrete work. Salary £550 to £700 per annum according to experience. Superannuation scheme available. Write to UDALLS, West Quay Road, Southampton, before July 31st.

SITUATION VACANT. DIESPEKER & Co. require for their precast department a designer-draughtsman, experienced and familiar with the design and calculations of reinforced concrete structures, with particular application to a new form of precast floor construction. Permanent, pensionable and progressive position. Write fully to DIESPEKER & Co. Ltd., Clifton House, Euston Road, London, N.W.1.

SITUATION VACANT. Draughtsman required in connection with development of prefabricated concrete farm buildings. Must be capable of producing perspectives, and a knowledge of reinforced concrete design would be an advantage. This is an appointment with plenty of scope and opportunity. Good salary offered to right applicant. Apply to CRENDON CONCRETE CO. LTD., Thame Road, Long Crendon, near Aylesbury, Bucks.

SITUATION VACANT. General foreman to control production of precast concrete units for all types of farm buildings and agricultural products in growing works near Thame, Oxfordshire. Write, stating age, experience, and salary required, to CRENDON CONCRETE CO. LTD., Thame Road, Long Crendon, near Aylesbury.

SITUATIONS VACANT. Detailer-draughtsmen and juniors required for varied reinforced concrete work. Five-days' week. Superannuation scheme. Moving shortly to new offices at Battersea. Write, stating experience, age, and salary required, to ROM RIVER CO. LTD., 90 Eversholt Street, London, N.W.1.

SITUATIONS VACANT. Engineers with specialised training in the design and execution of prestressed concrete projects are required for permanent employment in Rhodesia and the Union of South Africa. Free passages. Pension scheme. Excellent prospects. Full details to Box JU/43, c/o 95 Bishopsgate, London, E.C.2.

REINFORCED CONCRETE ENGINEERS & DRAUGHTSMEN

required urgently in our London Drawing Office. Excellent opportunities. Pension scheme. Applications to PERSONNEL MANAGER, RICHARD HILL LTD., Reinforced Concrete Engineers, P.O. Box 29, Middlesbrough.

(Continued on page Lxxix.)

ULTIMATE-LOAD DESIGN

" Ultimate-Load Theory Applied to the Design of Reinforced and Prestressed Concrete Frames."

By Professor A. L. L. BAKER, D.Sc., M.I.C.E.

96 Pages. 40 Illustrations. 9 Tables. Price 18s. (19s. by post).
\$4 in North America.

Design of reinforced and prestressed concrete by the Ultimate-Load Method has been used abroad for some years, and will be permitted in the next revisions of British and U.S.A. Codes of Practice for Reinforced Concrete. This book (probably the first in the English language) on design procedure according to this method discusses the probability of failure and its effects, and describes how a suitable factor of safety can be decided upon. The conception of plastic hinges enables full use to be made of this method.

(I) FACTOR OF SAFETY.—Definitions. Assumed strength of concrete. Factors affecting ultimate strength. Determining the factor of safety. Load factors of safety based on an assessment of conditions and consequences of failure.

(II) ULTIMATE STRENGTH IN BENDING OF REINFORCED AND PRESTRESSED BEAMS.—Basic assumptions. Balanced design. Derivation of general formulæ. Factors governing ultimate strength in bending. T-beams and I-beams. Example.

(III) PLASTIC DEFORMATIONS OF HINGES AND MEMBERS.—Tensile hinges. Compressive hinges. Values of EI in plastic, elastic, and cracked conditions. Effect of position of neutral axis.

(IV) THEORY OF PLASTIC HINGES AND THE ULTIMATE STRENGTH OF FRAMES.—Design procedure by trial and adjustment. Basic assumptions and explanatory notes. Selection of positions of hinges and values of bending moments. Examples of general method of checking and adjusting plastic hinges. Example.

(V) EXPRESSIONS FOR ROTATIONS OF PLASTIC HINGES.—Calculation of 4-bay frames. General analysis. Example.

(VI) EXAMPLES AND APPLICATIONS OF PLASTIC HINGES.—Continuous reinforced and prestressed beams. Prestressed precast beams. Arches and building frames. Load-factor method. Shearing stresses. Bending and compression. Plastic hinges in slender columns. Design of frames.

ORDER FORM

To CONCRETE PUBLICATIONS,
Ltd.,

14 DARTMOUTH STREET,
LONDON, S.W.1, England.

Please send.....copy (copies) of

" Ultimate-Load Theory Applied to the Design of Reinforced and Prestressed Concrete Frames," by
A. L. L. Baker.

19s. by post. 4 dollars in Canada and U.S.A.

A remittance for.....is enclosed.

BLOCK CAPITALS PLEASE

NAME

ADDRESS

.....

.....

Remittances from Canada and U.S.A. may be made in the ordinary way by drawing a check on the customer's bank made payable to Concrete Publications, Ltd., in dollars and cents or by International Money Order.

(Continued from page lxvii.)

SITUATIONS VACANT. Senior reinforced concrete designer-draftsmen required. Must be experienced in the design of foundations and structures. High salaries will be paid to suitable applicants. Modern semi-detached houses to let to senior experienced men. Grant towards removal expenses and allowance made until removal effected. Pension and insurance scheme. Apply **STAFF PERSONNEL MANAGER, ASHMORE, BENSON, PEASE & Co., Stockton-on-Tees.**

SITUATION VACANT. Detailer with some design experience in reinforced concrete and structural steelwork required in consulting engineer's office. Salary £600 to £800 according to age and experience, plus luncheon vouchers. Apply **R. F. GALBRAITH, Cromwell House, Fulwood Place, London, W.C.1.**

SITUATION VACANT. **W. & C. FRENCH LTD.** urgently require designer-detailer mainly for reinforced concrete design and detailing. Applicants must be keen to learn about new methods and types of construction. Apply in writing, stating age, salary required, and full details of experience, to **PERSONNEL MANAGER, 50 Epping New Road, Buckhurst Hill, Essex.**

PORT OF LONDON AUTHORITY

have vacancies in their **DRAWING OFFICE** for **TECHNICAL ASSISTANTS** of various grades, in the salary range of £645 to £956 per annum, for structural engineering designers and detailers. These scales are under review.

Minimum qualifications are the holding of the Ordinary National Certificate in appropriate subjects and at least 5 years' experience in a design drawing office. Higher National Certificate is required for the higher grades. Experience in the design and detailing of reinforced concrete is essential but knowledge of steelwork design will be an advantage.

For one vacancy, experience in the design of heating systems will be an advantage.

It is the Authority's policy to encourage Technical Assistants to study for higher qualifications and facilities are provided in suitable cases.

Applications giving age, qualifications, and full details of experience should be addressed to the **ESTABLISHMENT OFFICER, Port of London Authority, Trinity Square, London, E.C.3.**

NATIONAL COAL BOARD

CIVIL ENGINEER required by N.C.B.'s Reconstruction Department in London, with corporate membership of Institution of Civil Engineers or of Institution of Structural Engineers and five years' experience in design and construction of civil engineering and building works. Experience of structural steelwork and reinforced concrete practices, general building construction, roads and drainage, is required. Some knowledge of prestressed concrete an advantage. Range £814 to £1414. (Ref. No. X/474/2C.)

ASSISTANT CIVIL ENGINEER also required with two years' experience in a design office on structural work and general building construction. Preference given to applicants who have passed or who are preparing themselves for a professional qualification. Range £518 to £1014, but not less than £664 at age 25, with opportunities for promotion. (Ref. No. X/613/2C.)

Appointments (superannuable), according to qualifications and experience, within inclusive ranges stated. Write, stating age, education, qualifications and experience, to National Coal Board, Staff Department, Hobart House, Grosvenor Place, London, S.W.1, marking envelope with relevant X/Ref. No. before 2:20 July, 1957.

DOW-MAC (PRODUCTS) LTD.

Require

REINFORCED CONCRETE DESIGNERS (AND TRAINEES)

Terms of Employment:

1. Salary up to £1,200 per annum, dependent upon qualifications.
2. Pension Scheme.
3. Removal expenses paid.
4. One month's settling-in allowance.
5. Contract can follow three months' probationary period.
6. Training given in specialised prestressed and precast concrete work.

Write, giving full details, to

STAFF MANAGER,

DOW-MAC (PRODUCTS) LTD.,

Tallington, Stamford, Lincs.

Opportunities for careers in Reinforced Concrete...

on the staff of

BRC

There are vacancies for Reinforced Concrete Designers and Detailers at our Head Office and at most of our Design Offices in: **LONDON · BRISTOL · LEEDS · LIVERPOOL · NEWCASTLE · GLASGOW · DUBLIN** Designs for a wide variety of interesting work, including prestressed and shell concrete are prepared at all offices. Five day week—Pension Scheme. Top rate salaries are paid to Designers, Designer-Detailers and Detailers in accordance with ability and experience. Openings available for graduates and men with H.N.C. Apprenticeship scheme available for students of good educational standard.

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

Chief Engineer:

A. F. MASON, B.Sc., M.I.C.E., M.J.Struct.E., M.A.S.O.N

M-W.642

(Continued overleaf.)

(Continued from previous page.)

CENTRAL ELECTRICITY AUTHORITY HEADQUARTERS

Applications are invited for the appointment of CIVIL ENGINEERS at the RESEARCH LABORATORIES, LEATHERHEAD, SURREY, to carry out investigations into the properties of pulverised-fuel ash concrete, the applications of such concrete to civil engineering projects, and the further use of pulverised-fuel ash. Candidates should have a degree or H.N.C. in Civil Engineering, preferably with some practical experience. Salary £550-£995 per annum according to qualifications and experience. Applications stating age, experience, present position, and salary should be forwarded to D. MOFFAT, Director of Establishments, Winsley Street, London, W.1. Quote reference C.C.E./289.

SOUTHERN RHODESIA

A progressive, rapidly-expanding Company, specialising in the manufacture and erection of precast prestressed concrete structures, invites applications from young Engineers for THREE appointments of Assistant. Applicants should be professionally qualified at least in part by University Degree or H.N.C. and/or graduateship of an appropriate Chartered Institution. Exceptions may be considered in certain circumstances of outstanding experience. In addition to a thorough grounding of design and detailing of concrete structures generally, the following qualifications together or singly will be considered an advantage: (a) Practical experience on the site (b) Quality control of concrete through the medium of a Laboratory (c) Public relations as technical advisor.

Applications in writing only, stating age, education, marital status, qualifications, experience, with names of references, should be made in the first place to SUMNER, HARKER & Co. LTD., 196 Deansgate, Manchester, who will arrange for an interview in August with a Director from Rhodesia.

Salary offered will be not less than £100 per month with annual increments on the basis of a three years' contract.

Free air passage will be given to the Engineer, and assistance to his wife and family. Duties to commence early in October, 1957.

PERSIAN ROAD CONTRACT

JOHN MOWLEM & CO., LTD., HAVE A VACANCY IN THEIR ORGANISATION IN PERSIA FOR A STRUCTURAL ENGINEER FOR BRIDGE DESIGN. Applicants must be qualified and thoroughly experienced, particularly in the design of concrete structures and bridge work. Salary inclusive of allowances equivalent to approximately £3500 per annum.

THE TERM OF EMPLOYMENT FOR THE ABOVE VACANCY WOULD BE FOR A PERIOD OF TWO YEARS, RENEWABLE BY MUTUAL CONSENT. APPLICANTS SHOULD APPLY IN WRITING, GIVING BRIEF DETAILS OF THEIR EXPERIENCE, TO JOHN MOWLEM & CO., LTD., 123 VICTORIA STREET, LONDON, S.W.1.

SITUATIONS VACANT. SQUARE GRIP REINFORCEMENT Co., Keynsham, Bristol, have vacancies at Bristol and Birmingham for reinforced concrete designers to act as section leaders. Work covers a wide range of structures, and applicants should have had good previous experience. Good salary, profit-sharing scheme, pension, and five-days' week. Modern office in pleasant surroundings. Vacancies also for experienced detailers. Write in confidence, giving full details.

SITUATIONS VACANT. Reinforced concrete detailer required for interesting work. Keen men willing to learn design desired. Five-days' week. Apply HUNTER & DUNN, Consulting Engineers, 34 Smith Square, London, S.W.1. Telephone Abbey 6075.

SITUATION VACANT. Reinforced concrete designer-draftsman required by K. HOLST & Co. LTD., 10 Waddington Street, Durham City. Interesting and varied work in all types of structures. Salary in excess of A.E.S.D. rates. Bonus, and non-contributory pension scheme. Telephone Durham 4353.

ASSISTANT DESIGN ENGINEERS

Vacancies exist with the Engineering Branch of the Industrial Group of the United Kingdom Atomic Energy Authority at its Headquarters at Risley, Warrington, Lancs.

DUTIES:

- (a) Ref. 1898. To lead a small team of staff engaged on design of domestic, process and cooling water systems, drainage, roads, railways and building services associated with the Authority's construction programme, or to undertake individual design of a good standard
- (b) Ref. 1958. The preparation of calculations and detailed drawings for all types of structures in steel and/or reinforced concrete under the supervision of a structural engineer.

QUALIFICATIONS & EXPERIENCE:

Applicants must have:

- For Post (a) an honours degree in Civil Engineering followed by about 2 years' formal training or practical experience, and be taking active steps towards Corporate Membership of the Institution of Civil Engineers.
- For Post (b) a Higher National Certificate or equivalent qualification in Structural or Civil Engineering, and have had experience in the type of work involved.

Candidates should be at least 25 years of age, although younger candidates may be considered.

SALARY: will be assessed within the scale £795 to £1,210 per annum.

A contributory Pension Scheme is in operation.

Authority houses for renting by successful married candidates may be available in due course, or alternatively, substantial assistance may be given towards legal expenses incurred in private purchase.

Send a postcard for an application form, quoting the appropriate reference, to RECRUITMENT OFFICER, UNITED KINGDOM ATOMIC ENERGY AUTHORITY, Industrial Group Headquarters, Risley, Warrington, Lancs.

Closing Date: 29th July, 1957.





STONE COURT AGGREGATES




General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.

Special Specifications made to order.



STONE COURT BALLAST CO. LTD.
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Abbey 3456.



GLASGOW

NEWCASTLE

BELFAST

LIVERPOOL

MANCHESTER

DUBLIN

LEICESTER

STAFFORD

BIRMINGHAM

CARDIFF

BRISTOL

LONDON

BRE

*Specialists in Reinforced Concrete Design
and Suppliers of Reinforcement, with
Design and Branch Offices strategically
placed throughout the British Isles*

**REINFORCED CONCRETE IS
CONSTRUCTION AT ITS BEST**

There
are vacancies
for experienced
engineers in several
of our design offices.

The British Reinforced Concrete Engineering Co. Ltd., Stafford

M-W. 791

